



Rocky Flats Environmental Technology Site

RECONNAISSANCE LEVEL CHARACTERIZATION REPORT (RLCR)

BUILDINGS 125 AND 763, AND TRAILER 900C

GROUP 10 CLOSURE PROJECT

REVISION 0

Reviewed for Classification/UCNI/040
By: Janet Nesheim, Derivative Classifier
DOE, EMCBC
Date: 10-14-08
Confirmed Unclassified, Not UCNI/040

November 14, 2001



ADMIN RECORD

IA-A-000891

REVIEWED FOR CLASSIFICATION/UCNI
BY: C J FINEBODY - u/nm
DATE: 12/19/01

1/154

RECONNAISSANCE LEVEL CHARACTERIZATION REPORT (RLCR)


BUILDINGS 125 & 763, AND TRAILER 900C

GROUP 10 CLOSURE PROJECT

REVISION 0

November 14, 2001

Reviewed by:


Paul Miles, Quality Assurance

Date: 11/29/01

Reviewed by:


Michael Chritton, RISS ESH&Q Manager

Date: 11/30/01

Approved by:


Vern Guthrie, KH Project Manager

Date: 12/3/01

2

TABLE OF CONTENTS

| | |
|--|-----------|
| ABBREVIATIONS/ACRONYMS..... | IV |
| EXECUTIVE SUMMARY | V |
| 1 INTRODUCTION..... | 1 |
| 1.1 PURPOSE..... | 1 |
| 1.2 SCOPE..... | 1 |
| 1.3 DATA QUALITY OBJECTIVES | 1 |
| 2 HISTORICAL SITE ASSESSMENT..... | 2 |
| 3 RADIOLOGICAL CHARACTERIZATION AND HAZARDS..... | 2 |
| 4 CHEMICAL CHARACTERIZATION AND HAZARDS | 3 |
| 4.1 ASBESTOS..... | 3 |
| 4.2 BERYLLIUM (BE)..... | 3 |
| 4.3 RCRA/CERCLA CONSTITUENTS [INCLUDING METALS AND VOLATILE ORGANIC COMPOUNDS (VOCs)] | 4 |
| 4.4 POLYCHLORINATED BIPHENYLS (PCBS) | 4 |
| 5 PHYSICAL HAZARDS..... | 4 |
| 6 DATA QUALITY ASSESSMENT | 5 |
| 7 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES..... | 5 |
| 8 FACILITY CLASSIFICATION AND CONCLUSIONS | 6 |
| 9 REFERENCES..... | 7 |

ATTACHMENTS

- A Facility Location Map
- B Historical Site Assessment Reports
- C Radiological Data Summaries and Survey Maps
- D Chemical Data Summaries and Sample Maps
- E Data Quality Assessment (DQA) Detail

ABBREVIATIONS/ACRONYMS

| | |
|---------------------|---|
| ACM | Asbestos containing material |
| Be | Beryllium |
| CDPHE | Colorado Department of Public Health and the Environment |
| DCGL _{EMC} | Derived Concentration Guideline Level – elevated measurement comparison |
| DCGL _w | Derived Concentration Guideline Level – Wilcoxon Rank Sum Test |
| D&D | Decontamination and Decommissioning |
| DDCP | Decontamination and Decommissioning Characterization Protocol |
| DOE | U.S. Department of Energy |
| DPP | Decommissioning Program Plan |
| DQA | Data quality assessment |
| DQOs | Data quality objectives |
| EPA | U.S. Environmental Protection Agency |
| FDPM | Facility Disposition Program Manual |
| HVAC | Heating, ventilation, air conditioning |
| HSAR | Historical Site Assessment Report |
| IHSS | Individual Hazardous Substance Site |
| IWCP | Integrated Work Control Package |
| K-H | Kaiser-Hill |
| LBP | Lead-based paint |
| LLW | Low-level waste |
| MARSSIM | Multi-Agency Radiation Survey and Site Investigation Manual |
| MDA | Minimum detectable activity |
| MDC | Minimum detectable concentration |
| NORM | Naturally occurring radioactive material |
| NRA | Non-Rad-Added Verification |
| OSHA | Occupational Safety and Health Administration |
| PARCC | Precision, accuracy, representativeness, comparability and completeness |
| PCBs | Polychlorinated Biphenyls |
| PDS | Pre-demolition survey |
| QC | Quality Control |
| RCRA | Resource Conservation and Recovery Act |
| RFCA | Rocky Flats Cleanup Agreement |
| RFETS | Rocky Flats Environmental Technology Site |
| RFFO | Rocky Flats Field Office |
| RLC | Reconnaissance Level Characterization |
| RLCR | Reconnaissance Level Characterization Report |
| RSP | Radiological Safety Practices |
| SVOCs | Semi-volatile organic compounds |
| TCLP | Toxicity Characteristic Leaching Procedure |
| TSA | Total surface activity |
| VOCs | Volatile organic compounds |

4

EXECUTIVE SUMMARY

A Reconnaissance Level Characterization (RLC) was performed to enable facility "Typing" per the RFETS Decommissioning Program Plan (DPP; K-H, 1999) and compliant disposition and waste management of Group 10 facilities (i.e., Buildings 125 and 763 and Trailer 900C). Because these facilities were anticipated to be Type 1 facilities, the characterization was performed in accordance with the Pre-Demolition Survey Plan (MAN-127-PDSP). All facility surfaces were characterized in this RLC, including the interior and exterior surfaces (i.e., floors (slabs), walls, ceilings and roofs). Environmental media beneath and surrounding the facilities were not within the scope of this RLCR and will be addressed at a future date using the Soil Disturbance Permit process and in compliance with RFCA.

The RLC encompassed both radiological and chemical characterization to enable compliant disposition and waste management pursuant to the D&D Characterization Protocol (MAN-077-DDCP). The characterization built upon physical, chemical and radiological hazards identified in the facility-specific Historical Site Assessment Reports.

Results indicate that no radiological contamination exists in excess of the PDSP unrestricted release limits of DOE Order 5400.5, and no hazardous wastes. Building 125 contains both friable and non-friable asbestos. Fluorescent light ballasts may contain PCBs. Any PCB ballasts and asbestos containing materials will be managed and disposed of in compliance with Environmental Protection Agency (EPA) and Colorado Department of Public Health and Environment (CDPHE) regulations. All concrete associated with these facilities meet the criteria for recycling concrete per the RFCA RSOP for Recycling Concrete.

Based upon this RLCR and subject to concurrence by the CDPHE, Group 10 facilities are considered to be Type 1 facilities. To ensure that the facilities remain free of contamination and that RLC data remain valid, isolation controls have been established, and the facilities have been posted accordingly.

1 INTRODUCTION

A Reconnaissance Level Characterization (RLC) was performed to enable compliant disposition and waste management of Group 10 facilities (i.e., Buildings 125 and 763, and Trailer 900C). Because these facilities were anticipated to be Type 1 facilities, a PDS characterization was performed. All facility surfaces were characterized in this RLC, including the interior and exterior surfaces of the facilities (i.e., floors (slabs), walls, ceilings and roofs). Environmental media beneath and surrounding the facilities were not within the scope of this RLC Report (RLCR) and will be addressed at a future date using the Soil Disturbance Permit process and in compliance with RFCA.

As part of the Rocky Flats Environmental Technology Site (RFETS) Closure Project, numerous facilities will be removed. Among these are the Group 10 facilities. The locations of these facilities are shown in Attachment A, Facility Location Map. These facilities no longer support the RFETS mission and will be removed to reduce Site infrastructure, risks and/or operating costs.

Before the facilities can be removed, a Pre-Demolition Survey (PDS) must be conducted; this document presents the PDS results. The PDS was conducted pursuant to the Decontamination and Decommissioning Characterization Protocol (MAN-077-DDCP) and the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). The PDS is built upon physical, chemical and radiological hazards identified in the facility-specific Historical Site Assessment Reports.

1.1 Purpose

The purpose of this report is to communicate and document the results of the RLC effort. PDSs are performed before building demolition to define the final radiological and chemical conditions of a facility. Final conditions are compared with the release limits for radiological and non-radiological contaminants. PDS results will enable project personnel to make final disposition decisions, develop related worker health and safety controls, and estimate waste volumes by waste types.

1.2 Scope

This report presents the final radiological and chemical conditions of the Group 10 facilities. Environmental media beneath and surrounding the facilities are not within the scope of this RLCR and will be addressed using the Soil Disturbance Permit process and in compliance with RFCA.

1.3 Data Quality Objectives

The Data Quality Objectives (DQOs) used in designing this RLC were the same DQOs identified in the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). Refer to section 2.0 of MAN-127-PDSP for these DQOs.

6

2 HISTORICAL SITE ASSESSMENT

Facility-specific Historical Site Assessments (HSAs) were conducted to understand facility histories and related hazards. The assessments consisted of facility walkdowns, interviews, and document review, including review of the Historical Release Report (refer to the D&D Characterization Protocol, MAN-077-DDCP). Results were used to identify data gaps and needs, and to develop radiological and chemical characterization packages. Results of the facility-specific HSAs were documented in facility-specific Historical Site Assessment Reports (HSARs). Refer to Attachment B, Historical Site Assessment Report, for copies of the Group 10 HSARs. In summary, the HSAR identified no potential for radiological and chemical hazards, except the potential for asbestos containing materials and PCBs in paint and light ballasts.

3 RADIOLOGICAL CHARACTERIZATION AND HAZARDS

Group 10 facilities were characterized for radiological hazards per the PDSP. Radiological characterization was performed to define the nature and extent of radioactive materials that may be present on the facility surfaces. Measurements were performed to evaluate the contaminants of concern. Based upon a review of historical and process knowledge, building walk-downs, and MARSSIM guidance, a Radiological Characterization Plan was developed during the planning phase that describes the minimum survey requirements (refer to the RISS Characterization Project files for the Group 10 Radiological Characterization Plan). Radiological survey unit packages were developed for each survey unit. Survey unit identification numbers are as follows: G10001 – G10005. Each survey unit included the interior and exterior surfaces of the affected facility/structure. Individual radiological survey unit packages are maintained in the RISS Characterization Project files.

Group 10 survey unit packages were developed in accordance with Radiological Safety Practices (RSP) 16.01, *Radiological Survey/Sampling Package Design, Preparation, Control, Implementation and Closure*. Total surface activity (TSA), removable surface activity (RSA), and scan measurements were collected in accordance with RSP 16.02 *Radiological Surveys of Surfaces and Structures*. Radiological survey data were verified, validated and evaluated in accordance with RSP 16.04, *Radiological Survey/Sample Data Analysis*. Quality control measures were implemented relative to the survey process in accordance with RSP 16.05, *Radiological Survey/Sample Quality Control*. Radiological survey data, statistical analysis results, survey locations, and radiological scan maps are presented in Attachment C, Radiological Data Summary and Survey Maps.

A total of 152 TSA measurements, 152 RSA measurements, and 5% scan surveys were performed on the three Group 10 facilities. Four survey locations in Survey Unit G10-002 (B763 exterior) initially indicated gross alpha TSA above or near the DCGL_w. These four survey locations were sealed and allowed to decay overnight. Follow-up surveys gave gross alpha TSA readings below the DCGL_w, indicating that the previous measurements were not due to DOE-added material and were most likely due to radon daughter products. None of the other measurements indicated elevated activity above the appropriate DCGL_w values. Therefore, the PDS confirmed the indicated facilities do not contain radiological contamination above the surface contamination guidelines provided in the RFETS PDSP for D&D Facilities. Isolation control postings are displayed on affected structures to ensure no radioactive materials are introduced.

4 CHEMICAL CHARACTERIZATION AND HAZARDS

Group 10 facilities were characterized for chemical hazards per the PDSP. Chemical characterization was performed to determine the nature and extent of chemical contamination that may be present on or in these facilities. Based upon a review of historical and process knowledge, visual inspections, and PDSP DQOs, additional sampling needs were determined. A Chemical Characterization Plan (refer to RISS Characterization Project files for the Group 10 Chemical Characterization Plan) was developed during the planning phases that describes sampling requirements and the justification for the sample locations and estimated sample numbers. Contaminants of concern included asbestos, beryllium, RCRA/CERCLA constituents, and PCBs. Refer to Attachment D, Chemical Summary Data and Sample Maps, for details on sample results and sample locations. Isolation control postings are displayed on affected structures to ensure no hazardous materials are introduced.

4.1 Asbestos

Building 763 and Trailer 900C were inspected by a CDPHE-certified inspector in accordance with the PDSP. No building materials suspected of containing asbestos were located. Therefore, no bulk samples were taken for PLM analysis.

In 1996, a comprehensive asbestos inspection was conducted in Building 125 (refer to "Asbestos Inspection and Operations and Maintenance Plan for Building 125," by SITEX Environmental, Inc., December 31, 1996 in Attachment D). The sample results revealed the presence of both friable and non-friable asbestos containing materials. Subsequent to the initial PDS walk-down and review of the inspection results, several asbestos data gaps were identified. Therefore, bulk samples were obtained of the interior window caulking and the exterior caulking of the sheet-metal siding. Samples were obtained by a CDPHE-certified asbestos inspector in accordance with the *Asbestos Characterization Protocol, PRO-563-ACPR, Revision 0*. The window caulking contained *trace* amounts of asbestos (<1% by *point count*), and the exterior caulking contained >1% asbestos from 1.25% to 4% by *point count*. Sampling results and locations are presented in Attachment D.

4.2 Beryllium (Be)

Based on the HSARs and personnel interviews, these buildings were anticipated Type 1 facilities. There is not, however, adequate historical and process knowledge to conclude that beryllium was not used or stored in these buildings. Therefore, biased beryllium sampling was performed in accordance with the PDSP and the *Beryllium Characterization Procedure, PRO-536-BCPR, Revision 0, September 9, 1999*. Biased sample locations corresponded with the most probable areas of dust accumulation (including beryllium dust), assuming airborne deposition.

All beryllium sample results were less than 0.1 $\mu\text{g}/100\text{cm}^2$. Beryllium sample data and sample location maps are contained in Attachment D, Chemical Data Summaries and Sample Maps.

8

4.3 RCRA/CERCLA Constituents [including metals and volatile organic compounds (VOCs)]

Based on the Group 10 HSARs, interviews and facility walkdowns, there is no reasonable likelihood that RCRA/CERCLA constituents have contaminated the three facilities. Therefore, RCRA/CERCLA constituent sampling was not performed in these facilities. Mercury vapor lights and lead shielding will be removed prior to demolition.

Sampling for lead in paint in the Group 10 facilities was not performed. Environmental Waste Compliance Guidance #27, *Lead-based Paint (LBP) and Lead-based paint Debris Disposal*, states that LBP debris generated outside of currently identified high contamination areas shall be managed as non-hazardous (solid) wastes, and additional analysis for characteristics of hazardous waste derived from LBP is not a requirement for disposal.

4.4 Polychlorinated Biphenyls (PCBs)

Based on the Group 10 HSARs, interviews and facility walkdowns, no PCB-containing equipment were ever present in Building 763 and Trailer 900C, and therefore, there is no potential for PCB contamination in these facilities resulting from spills. Therefore, PCB sampling was not performed in these facilities. In addition, based on the age of the facilities (constructed after 1980), paints do not contain PCBs.

Stains in the Building 125 concrete were sampled and analyzed for PCBs. Sampling and analysis results show no PCB contamination. Sample data and locations are presented in Attachment D. Based on the age of B125 (constructed in 1965), some paints may contain PCBs. Painted demolition debris from Building 125 will either be disposed of as PCB Bulk Product Waste, or, if meeting the release criteria for all other constituents as noted in the Concrete RSOP, the concrete will be used as backfill onsite.

Some facilities may contain fluorescent light ballasts that contain PCBs. Therefore, fluorescent light fixtures will be inspected to identify PCB ballasts during removal operations. PCB ballasts will be identified based on factors such as labeling (e.g., PCB-containing and non-PCB-containing), manufacturer, and date of manufacturing. All ballasts that do not indicate non-PCB-containing are assumed to be PCB-containing.

5 PHYSICAL HAZARDS

Physical hazards associated with Group 10 facilities consist of those common to standard industrial environments and include hazards associated with energized systems, utilities, and trips and falls. There are no unique hazards associated with the facilities. The facilities have been relatively well maintained and are in good physical condition, and therefore, do not present hazards associated with building deterioration. Physical hazards are controlled by the Site Occupational Safety and Industrial Hygiene Program, which is based on OSHA regulations, DOE orders, and standard industry practices.

6 DATA QUALITY ASSESSMENT

Data used in making management decisions for decommissioning of Group 10 facilities, and consequent waste management, are of adequate quality to support the decisions documented in this report. The data presented in this report (Attachments C and D) were verified and validated relative to DOE quality requirements, applicable EPA guidance, and original DQOs of the project.

In summary, the Verification and Validation (V&V) process corroborates that the following elements of the characterization process are adequate:

- ♦ the *number* of samples and surveys;
- ♦ the *types* of samples and surveys;
- ♦ the sampling/survey process as implemented "in the field"; and,
- ♦ the laboratory analytical process, relative to accuracy and precision considerations.

Details of the DQA are provided in Attachment E.

7 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES

The demolition and disposal of Group 10 facilities will generate a variety of wastes. Estimated waste types and waste volumes are presented below by facility. All wastes can be disposed of as sanitary waste, except asbestos containing material and PCB Bulk Product Waste. There is no radioactive or hazardous waste. Asbestos and PCB ballasts will be managed pursuant to Site asbestos and PCB abatement and waste management procedures.

| Waste Volume Estimates and Material Types, Group 10 | | | | | | | |
|---|--|-----------------|------------------|--------------------------------------|--------------------------|------------------------------------|------------------------|
| Facility | Concrete (cu ft) | Wood (cu ft) | Metal (cu ft) | Corrugated Sheet Metal (cu ft) | Wall Board (cu ft) | ACM (cu ft) | Other Waste (cu ft) |
| B125 | 15,000 | 300 | 3,400 | 1,600 | 600 | 1,080 friable 5,400 non-friable | 11,600 |
| B763 | 6,300 | 300 | 600 | 1,000 | 0 | 0 | 900 |
| T900C | No waste will be generated; trailer will be sold and returned to commerce. | | | | | | |

8 FACILITY CLASSIFICATION AND CONCLUSIONS

Based on the analysis of radiological, chemical and physical hazards, Group 10 facilities (i.e., Buildings 125 and 763, and Trailer 900C) are classified as RFCA Type 1 facilities pursuant to the RFETS Decommissioning Program Plan (DPP; K-H, 1999). The Type 1 classification is based on a review of historical and process knowledge, and newly acquired RLC data, and will be subject to concurrence by the Colorado Department of Public Health and the Environment (CDPHE).

The RLC of the Group 10 facilities was performed in accordance with the DDCP and PDSP, all PDSP DQOs were met, and all data satisfied the PDSP DQA criteria. These facilities do not contain radiological or hazardous wastes. PCB ballasts and asbestos containing material will be removed and disposed of in compliance with EPA and CDPHE regulations. Environmental media beneath and surrounding the facilities will be addressed at a future date using the Soil Disturbance Permit process and in compliance with RFCA. All concrete associated with these facilities meet the criteria for recycling concrete per the RFCA RSOP for Recycling Concrete.

To ensure that the Type 1 facilities remain free of contamination and that RLC data remain valid, isolation controls have been established, and the facilities are posted accordingly.

11

9 REFERENCES

- DOE/RFFO, CDPHE, EPA, 1996. Rocky Flats Cleanup Agreement (RFCA), July 19, 1996.
- DOE Order 5400.5, "Radiation Protection of the Public and the Environment."
- DOE Order 414.1A, "Quality Assurance."
- EPA, 1994. "The Data Quality Objective Process," EPA QA/G-4.
- K-H, 1999. Decommissioning Program Plan, June 21, 1999.
- MAN-131-QAPM, *Kaiser-Hill Team Quality Assurance Program*, Rev. 0, November 15, 2000.
- MAN-076-FDPM, *Facility Disposition Program Manual*, Rev. 1, September 1999.
- MAN-077-DDCP, *Decontamination and Decommissioning Characterization Protocol*, Rev. 3, April 23, 2001.
- MAN-127-PDSP, *Pre-Demolition Survey Plan for D&D Facilities*, Rev. 0, April 23, 2001.
- MARSSIM - Multi-Agency Radiation Survey and Site Investigation Manual, December 1997 (NUREG-1575, EPA 402-R-97-016).
- PRO-475-RSP-16.01, *Radiological Survey/Sampling Package Design, Preparation, Control, Implementation, and Closure*, Rev. 1, May 22, 2001.
- PRO-476-RSP-16.02, *Pre-Demolition (Final Status) Radiological Surveys of Surfaces and Structures*, Rev. 1, May 22, 2001.
- PRO-477-RSP-16.03, *Radiological Samples of Building Media*, Rev. 1, May 22, 2001.
- PRO-478-RSP-16.04, *Radiological Survey/Sample Data Analysis for Final Status Survey*, Rev. 1, May 22, 2001.
- PRO-479-RSP-16.05, *Radiological Survey/Sample Quality Control for Final Status Survey*, Rev. 1, May 22, 2001.
- PRO-563-ACPR, Asbestos Characterization Procedure, Revision 0, August 24, 1999.
- PRO-536-BCPR, Beryllium Characterization Procedure, Revision 0, August 24, 1999.
- RFETS, Environmental Waste Compliance Guidance #25, Management of Polychlorinated Biphenyls (PCBs) in Paint and Other Bulk Product Waste During Facility Disposition.
- RFETS, Environmental Waste Compliance Guidance #27, Lead-Based Paint (LBP) and Lead-Based Paint Debris Disposal.
- RFCA Standard Operation Protocol for Recycling Concrete, September 28, 1999.
- RFETS, Historical Site Assessment for Group 10, August 2001.


12

ATTACHMENT A

Facility Location Map

Building Cluster 125, 763, 1900C

Standard Map Features



Buildings and other structures



Solar Evaporation Ponds (SEPs)



Lakes and ponds

Streams, ditches, or other
drainage features

Fences and other barriers

Paved roads

Dirt roads

DATA SOURCE BASE FEATURES:

Buildings, fences, hydrography, roads and other
structures from 1994 aerial fly-over data
captured by EG&G RSL, Las Vegas.
Digitized from the orthophotographs, 1/95



Scale = 1 : 12450
1 inch represents approximately 1038 feet
0 500 1000
Feet
State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

as of: 200-066-7707

Prepared for:



DynCorp

THE ART OF TECHNOLOGY

MAP ID: FY 2002

October 22, 2001

ATTACHMENT B

Historical Site Assessment Report

D&D RISS Facility Characterization Historical Site Assessment Report

Facility ID: Building 125, Standards Laboratory

Anticipated Facility Type (1, 2, or 3): Building 125 = Type 1

Refer to attached site drawing for facility location.

This facility – specific Historical Site Assessment (HSA) has been performed in accordance with:

D&D Characterization Protocol, RFETS MAN-077-DDCP, latest version, and

Facility Disposition Program Manual, RFETS MAN-076-FDPM, latest version

Physical Description

The Building 125 Standards Lab is a single-story, pre-engineered, metal-frame building on a concrete foundation and floor. Building 125 is located immediately north of the 215A Water Tower and adjacent to Third Street. Building 125 was constructed and put into service in 1965. The exterior walls are tan color enamel corrugated steel panels sandwiched over 3" of fiberglass insulation. Building 125 is a rectangular-shaped facility with dimensions of approximately 187' X 90' X 16' high at the roof eve, 25' high at the roof peak. The roof is corrugated steel panels over 3" batting insulation. The metal roof of Building 125 is also painted a tan color. The square footage of Building 125 is approximately 16,830 square. Building 125 has numerous floor drains connected to the plant sewer system. Building 125 has fourteen roof drain downspouts, seven on the west roof eve and seven on the east roof eve. The interior walls are concrete block, gypsum board, or stainless steel/polystyrene panels. The office area of Building 125 is partitioned with Transite® and steel-stud construction. Most hallways, rooms, and labs have the drop-ceilings with metal ceiling tiles, however some hallways and offices have the drop-ceilings with acoustical ceiling tiles. Building 125 has 5 entry doors. Door 1 is a personnel entry door on the north side. Door 2 is a ground-level dock door in the southeast corner of the building with an I-beam and chain hoist and double metal doors each 4' X 8'. Door 3 is a 4' X 7' double personnel entry door with wire glass panes in the upper half of the door. Door 4 is an 8' wide X 10' high rollup metal door leading into the south end of Building 125 Utility Room 125. Door 5 is personnel entry door on the northwest corner of Building 125.

Building 125 has general building HVAC systems for human comfort and specialized HVAC systems for precise climate control of some of the calibration laboratories. No specialized off-gas cleanup or filtering systems are necessary because the only airborne hazardous materials are small quantities of vapor released from volatile cleaning agents (ethanol and freon). The HVAC system interfaces with the steam, electrical, and compressed air systems. There are several window-mounted refrigeration-type air conditioning units. In addition, the dock area, Room 109, has two roof-mounted refrigeration-type air conditioning units.

Building 125 electrical power is provided by a 13.8-kV distribution system via a 13.8-kV/480-V transformer located west of the building. The 480-V power is provided to appropriate transformers and electrical distribution equipment in Room 125. There are no emergency or backup electrical power systems required for safe facility operation. Self-contained, battery-powered emergency lighting is provided for emergency egress. The exterior south and west walls each contain two lighting fixtures that appear to be mercury vapor lights.

Approximately ten percent of Building 125 is protected by a wet-pipe sprinkler system. The system is fed from a 4-inch firewater line in Room 125 from the west side of the building. The post indicator valves (PIVs) located outside the building have protective posts in the ground to prevent vehicle impacts. There is also an exterior fire department connection on the west wall of Room 125.

Building 125 has 125-psi steam from the Site distribution system to support the heating needs. Building 125 domestic cold water is distributed throughout the building. Building 125 has a LSDW System with speakers in all areas of the facility. Building 125 is connected to the Plant sanitary sewer system, and all floor drains, rest room facilities, and chemical lab bench sinks are connected to the sanitary sewer system. There are no process sinks or process drains in Building 125. Regulated liquid wastes are disposed of via site support services. Used oils and other non-regulated liquids are stored in drum or waste

D&D RISS Facility Characterization Historical Site Assessment Report

Physical Description (Con't)

containers. Compressed air (95 psi) is used throughout Building 125, provided by various compressors in the facility. Filtration systems are used to clean and dry air. Liquid nitrogen was supplied from a large tank, Tank 079, which was located to the east of Building 125. Liquid Nitrogen Tank 079 was removed in June 2001, but the concrete pad remains. The liquid nitrogen lines supplied liquid nitrogen for low-temperature calibration equipment via a manifold and vacuum system cold traps via portable dewars.

Building 125 has several interfaces with other areas, facilities, systems, processes and operations. Building 125 interfaces with the site utility systems (natural gas, electric, and water, etc.). A back-up air compressor is located in Room 125 that supplies approximately eight other nearby buildings.

Historical Operations

Specific work areas include Rooms 104, 105, 110, and 111 were laboratory and calibration areas. Room 114 was the Chemistry Standards Laboratory. Rooms 115, 116, 117, 118, and 119 were modular labs or specialized labs that required precise climate controls. Room 103 was a computer room. Room 109 was the receiving/shipping and storage room. This area is used to store flammable materials in fire-resistant storage cabinets. A system of monorails was used to move materials in and out of Room 109. Room 125 contains an HVAC, air compressors, and other building required utilities. Liquid nitrogen was supplied from a large tank, Tank 079, which was located to the east of Building 125. Liquid Nitrogen Tank 079 was removed in June 2001, but the concrete pad remains.

Building 125 Standards Laboratory is included in the Historic American Engineering Record. Building 125 is included in the Site Historical Release Report, PAC 100-2 and UBC 125. Building 125 Standards Laboratory has a Safety Analysis Report (SAR), which is included in Volume II of Site SAR. Building 125 has a WSRIC Book for all the calibration and other processes that were operated in the building. Building 125 does not have any tanks or areas on the Master Listing of RCRA Units. The Building 125 is not on the Listing of Beryllium Areas, Historical and Present. Engineering Drawings exist for the Building 125 Standards Laboratory.

Contaminants of Concern

Asbestos

Describe any potential, likely, or known sources of asbestos:

The original construction in 1965 contains Transite® and Gypsum® wall panels and 9" X 9" asbestos-containing floor tiles throughout the offices, lab rooms, and other work rooms. Asbestos insulation may have been used on steam, steam condensation, and hot domestic water pipes in Building 125. All entry doors into Building are posted with the standard ACM warning signs.

Asbestos data exists in the Plant Industrial Hygiene Asbestos Library, T-130B east of Cubicle 62. The Building 125 Asbestos Maintenance Plan, Sampling Plan, and Asbestos Sampling Results are contained in the Building 125 Asbestos Book, which is dated December 31, 1996.

D&D RISS Facility Characterization Historical Site Assessment Report

Beryllium (Be)

Describe any potential, likely, or known Be production or storage locations:

There were no known, likely, or potential beryllium production or storage areas in Building 125. Some equipment items shipped to Building 125 for calibration potentially could have been contaminated with Be. Equipment being shipped out of Building 125 was routinely smear checked for Be contamination; none of the three interviewees remembers the smear checks being positive for Be. The Building 125 is not on the Listing of Beryllium Areas, Historical and Present.

Summarize any recent Be sampling results: None of the people interviewed knew of any Be sampling that was ever conducted in Building 125.

Lead

Describe any potential, likely, or known sources of Lead (e.g., paint, shielding, etc.):

Building 125 does not have any lead shielding, but numerous lead bricks were used for counter weights in several of the lab rooms. During an August 2001 walkdown tour, no lead of any kind was found. Building 125 was constructed in 1965; and the many painted areas both inside and outside may have been painted with lead-based paints. Lead solder may have been used in electrical connections in Building 125.

RCRA/CERCLA Constituents

Describe any potential, likely, or known sources of RCRA/CERCLA constituents (e.g., chemical storage, waste storage, processes):

During the operation of the Building 125 Standard Laboratories, many chemicals were used and stored in various storage cabinets and lab areas. The main chemical storage cabinets were in Room 109, which is the dock and receiving/shipping area. Other Building 125 labs and work area rooms contained small satellite chemical storage areas. Building 125 contained no regulated liquid waste storage. Site support services are utilized for removal of RCRA waste from Building 125.

The interviewees had no knowledge of sources of RCRA/CERCLA constituents.

The Building 125 exterior south and west walls each contain two lighting fixtures that appear to be mercury vapor lights. Building 125 does not have any tanks or areas that are listed on the Master Listing of RCRA Units. Building 125 does not have any equipment that is listed in the Appendix 1 – Idle Equipment With Hazardous Materials Inventory. Building 125 does not have any equipment that is listed in the Appendix 1A – Idle Equipment With Non-Hazardous Materials Inventory.

Describe any potential, likely, or known spill locations (and sources, if any):

During approximately 35 years of Standards Laboratory operations, chemical and mercury spills occurred in the labs and dock areas of Building 125.

Describe methods in which spills were mitigated, if any:

Chemical and mercury spills were cleaned up using approved methods (historically every visible drop of mercury was picked up and re-contained).

D&D RISS Facility Characterization Historical Site Assessment Report

PCBs

Describe any potential, likely, or known sources of PCBs (e.g., light Ballasts, paints, equipment, etc.):
Power transformers, light ballasts, and paints used in the Building 125 could contain PCBs.

Describe any potential, likely, or known spill locations (and sources, if any):
Interviewees had no knowledge of PCBs and/or spills of PCBs.

Describe methods in which spills were mitigated, if any:
Interviewees had no knowledge of PCBs and/or spills of PCBs, therefore mitigation would not have been required.

Radiological Contaminants

Describe any potential, likely, or known radiological production or storage locations:

Interviewees had no knowledge of any radiological production areas at the Building 125. The only radioactive postings found in Building 125 during the walkdown tour was on the locked door of Room 113. Room 113 was said to have contained sealed sources that were removed from equipment in the various labs of Building 125. Room 113 still contains sealed pieces of depleted uranium and contaminated pieces of equipment found during strip-out of the Building 125 labs, as of August 22, 2001, as per Richard A. Link.

Room 119, of Building 125, was posted as a Radiation Monitored Area (RMA) from approximately 2000 until 2001 because of suspect internally contaminated equipment being stored there (this suspect internally contaminated equipment was consolidated into this one room from throughout Building 125). As of August 1, 2001, all of the suspect internally contaminated equipment has been removed from Room 119 of Building 125.

Describe any potential, likely, or known spill locations (e.g., known leaking sealed radioactive sources, leaking waste drums, potentially contaminated drains, etc.):

Describe methods in which spills were mitigated, if any:

One interviewee (Richard A. Link) said that historically the Chemical Standards Laboratories made up low-level radioactive standards for various labs on Plant Site. Mr. Link said that during the preparation of these standards, spills might have occurred but that he no personal knowledge of such a spill. If low-level spills occurred, they would have been cleaned up using approved cleanup methods, as per Mr. Link.

No other interviewee had knowledge of radioactive materials having been spilled within Building 125.

Other interviewees had no knowledge of radioactive materials of any kind at the Building 125 Site; therefore spill mitigation would not have been required.

Describe any potential, likely, or known isotopes of concern (e.g., weapons grade plutonium, uranium isotopes, pure Beta emitters, mixed fission products, etc.):

Historically sealed sources of Pu 238 and cesium were used and stored in Building 125. These sources have long since been removed (removal dates unknown).

Describe any potential, likely, or known external facility contamination (e.g., stack release points, unfiltered ventilation, facility's physical location to known site releases, etc.):

D&D RISS Facility Characterization Historical Site Assessment Report

Radiological Contaminants (Cont't)

Interviewees had no knowledge of radioactive materials spills of any kind within Building 125; therefore an answer to this statement does not apply.

Describe any process waste lines associated with the facility, if any (Are any abandoned? Capped?)

There are no process waste lines in Building 125. Building 125 never had any process waste lines. Therefore Building 125 has no abandoned or capped process waste lines.

Environmental Restoration Concerns

Describe any ER concerns that could affect facility characterization (e.g., IHSSs, PACs, UBCs):

Building 125 is under UBC-125. Nick Demos, ER Site Manager, stated that the UBC is designated because of the historical mercury inventory and because of mercury spills that occurred.

Interviewees had no knowledge of any other ER concerns for the Building 125 Site that could affect facility characterization. It was determined that PAC 100-606 needed no further action (refer to HRR).

Additional Information

Describe any additional information that may be useful during facility characterization (e.g., contaminant migration routes, waste-handling operations, physical hazards, Historical Release Reports, WSRIC data, etc.):

Interviewees had no knowledge of any additional information that may be useful during facility characterization. There is very little HRR information concerning Building 125. Extensive WSRIC books exist for Building 125, but the labs for which they were written no longer exist.

References

Provide all sources of information utilized to gather data for facility history (e.g., documents, files, interviews). Attach all applicable supporting documentation.

References used were: HRR, Site SAR, IHSS/PAC/UBC Site Maps, Listing of Beryllium Areas, Historical and Present, the T-130B Industrial Hygiene Asbestos Inventory Library, Building 125 Engineering Drawings, Appendix 1 of Idle Equipment With Hazardous Materials Inventory, Master Listing of RCRA Units, and Appendix 1A of Idle Equipment With Non-Hazardous Materials Inventory, the Building 125 WSRIC Books, and Historic American Engineering Record for the RFETS Building 125 Standard Laboratory.

Waste Volume Estimates and Material Types Building 125

| Concrete (cu ft) | Wood (cu ft) | Metal (cu ft) | Corrugated Sheet Metal (cu ft) | Wall Board (cu ft) | ACM | Other Waste |
|---------------------|-----------------|------------------|--------------------------------------|-----------------------|---|--|
| 15,021 | 300 | 3,397 | 1,572 | 576 | Transite - 772 cu ft Floor Tile - 53 cu ft | Glass 5cu ft Al - 118 cu ft Insul. 11,057 cu ft Ceramic tile - 9 cu ft Accoust. ceil. tile - 160 cu ft Accoust. wall - 241cu ft |

Further Actions

Recommend any further actions, if any (e.g., characterization, decontamination, special handling, etc.):

Interviewees had no further actions or recommendations concerning the characterization of the Building 125. The author of this RISS HSA Report has no further actions or recommendations concerning the characterization of the Building 125.

20

D&D RISS Facility Characterization Historical Site Assessment Report

Further Actions

Recommend any further actions, if any (e.g., characterization, decontamination, special handling, etc.):

Interviewees had no further actions or recommendations concerning the characterization of the Building 125. The author of this RISS HSA Report has no further actions or recommendations concerning the characterization of the Building 125.

Note:

This HSA was performed prior to SME walkdowns, and chemical and radiological characterization package preparations. Information contained in this HSA only represents a "snapshot" in time. Subsequent data may be obtained during SME walkdowns and chemical and radiological characterization package preparations, which may conflict with this report. However, this report will not be amended, and the newer data will take precedence over the data in the report. Newer Data will appear in the RLCR/PDSR

Prepared By:

Bob Sheets

Print Name

Signature

Date

D&D RISS Facility Characterization Historical Site Assessment Report

Facility ID: Building 763, South Breezeway, Portal 1 to Building 750

Anticipated Facility Type (1, 2, or 3): Building 763 = Type 1

Refer to attached site drawing for facility location.

This facility – specific Historical Site Assessment (HSA) has been performed in accordance with:

D&D Characterization Protocol, RFETS MAN-077-DDCP, latest version, and

Facility Disposition Program Manual, RFETS MAN-076-FDPM, latest version

Physical Description

Building 763, south breezeway in between Portal 1 and Building 750, is a single-story, aboveground tunnel/covered walkway building with masonry exterior walls on a poured reinforced concrete foundation and floor. Building 763 is approximately 316' long X 10' wide X 12' high. The square footage of Building 763 is approximately 3,160 square feet. Building 763 has three 3' X 7' metal double entry doors with 1/4" X 24" X 34" tempered safety glass in each door (one set of double doors on the south side, one set of double doors on the north side, and one set of double doors on the east side). The roof and concrete block walls extend approximately 4 feet beyond the entry doors on the south and north providing covered entryways. Both the south and north covered entryways have "wind clean-out" openings. The roof of Building 763 is flat and has three sections because the building is on a slight incline to the north. The middle roof section of Building 763 is approximately 18 inches higher than the south section; and the north roof section is approximately 18 inches higher than the middle roof section. The south and east roof edge of Building 763 has out-rigger fence posts every six feet approximately three feet high, tilting outward, with three strands of barbwire installed for security. Building 763 has a corrugated metal roof supported by steel I-beams. The metal roof is covered with 1-1/2 inches rigid insulation (assumed to be rigid Styrofoam® sheets) and .060 inches EPDM sheeting (Ethylene Propylene Diene Monomer). All edges of the roof are covered with galvanized metal flashing. The metal roofing and metal roof flashing are nailed to bolted down wood.

Building 763 is not a heated building and does not have a ventilation system, but the east wall has sixteen, 8" X 18" extruded aluminum louvered vents (non-operating) to the outside (8 near floor and 8 near ceiling/roof level). Building 763 has sixteen 2' X 4' fixed aluminum sash windows with Lexan® (thermoplastic carbonate-linked polymers) glazing in the east wall. Building 763 has thirteen overhead 8-foot 4-tube fluorescent light fixtures.

Building 763 does not have any floor drains, but it does have one storm sewer manhole cover in the floor, which is located near the west wall in the south half of the building.

Historical Operations

The construction of Building 763 was completed in December 1980, and the facility was put into service in January 1981. Building 763 has always been used as a covered walkway/tunnel from Portal 1 to Buildings 707, 750, 776 and 778. For approximately three years Building 763 was also used as a dosimeter badge/exchange facility in addition to the covered walkway/tunnel. During the time the facility was used as a dosimeter storage/exchange facility, Dosimeter Badge Storage Racks were installed on the east and west walls for approximately 2/3 of the north section of the facility. The Dosimeter Storage Racks have since been removed.

D&D RISS Facility Characterization Historical Site Assessment Report

Current Operational Status

Two interviewees agreed that the Building 763 facility is still fully operational and that it is still used for what it was designed for, protecting employees from severe weather conditions while walking from Portal 1 to their respective work building. Building 763 is not included in the Site Historical Release Report, but land/soils has an IHSS/PAC history. Building 763 does not have a Safety Analysis Report. Building 763 does not have a WSRIC, and it does not have any tanks or areas on the Master Listing of RCRA Units. Building 763 is not on the List of Beryllium Areas, Historical and Present. Engineering Drawings and Construction Drawings exist for Building 763.

Contaminants of Concern

Asbestos

Describe any potential, likely, or known sources of Asbestos: Building 763 is not posted as having asbestos containing materials (ACM). There are no known building-specific asbestos reports for Building 763.

Beryllium (Be)

Describe any potential, likely, or known Be production or storage locations: There are no postings referring to Be areas anywhere on any of the doors or walls of Building 763. Interviewees said that they had no knowledge of any Be being anywhere in or passing through Building 763. The Building 763 does not appear on the List of Beryllium Areas, Historical and Present.

Summarize any recent Be sampling results: Neither of the people interviewed knew of any Be sampling that was ever conducted in Building 763.

Refer to Characterization Package and RLC/PDSR.

Lead

Describe any potential, likely, or known sources of Lead (e.g., paint, shielding, etc.): The interior concrete block walls of Building 763 are painted with an off-white paint; the exterior walls of Building 763 are painted brown. The facility was constructed in 1980, and it is not known if lead-based paints were used on the interior or exterior walls. Therefore, lead-based paints might have been used. There is no lead shielding (no need for it) in Building 763. Lead solder may have been used in the metal flashing on the roof and in electrical connections within Building 763.

D&D RISS Facility Characterization Historical Site Assessment Report

RCRA/CERCLA Constituents

Describe any potential, likely, or known sources of RCRA/CERCLA constituents (e.g., chemical storage, waste storage, processes): The interviewees had no knowledge of sources of RCRA/CERCLA constituents, except lighting. Building 763 has three mercury-vapor exterior doorway lights. Building 763 has 13 8-foot 4-tube fluorescent lighting fixtures. Building 763's three exterior mercury lighting lamps are known to contain mercury. Interviewees did not know if the ballasts in the fluorescent lighting fixtures contain any PCB. Building 763 does not have any tanks or areas that are listed on the Master Listing of RCRA Units. Building 763 does not have any equipment that is listed in the Appendix 1 – Idle Equipment With Hazardous Materials Inventory. Building 763 does not have equipment that is listed in the Appendix 1A – Idle Equipment With Non-Hazardous Materials Inventory.

Building 763 is not mentioned in the Site SAR. There is no SAR for Building 763. A WSRIC was never written for Building 763.

Describe any potential, likely, or known spill locations (and sources, if any): Neither of the interviewees had any knowledge of any spills of any kind that ever occurred in Building 763.

Describe methods in which spills were mitigated, if any: Neither of the interviewees had any information of any spills ever occurring in Building 763, therefore, spill mitigation was never required.

PCBs

Describe any potential, likely, or known sources of PCBs (e.g., light ballasts, paints, equipment, etc.): The Building 763 lighting ballasts and paints potentially could contain PCBs. Building 763 does not have any power transformers.

Describe any potential, likely, or known spill locations (and sources, if any): Interviewees had no knowledge of PCBs and/or spills of PCBs in Building 763.

Describe methods in which spills were mitigated, if any: Interviewees had no knowledge of PCBs and/or spills of PCBs, therefore, mitigation was never required.

D&D RISS Facility Characterization Historical Site Assessment Report

Radiological Contaminants

Describe any potential, likely, or known radiological production or storage locations: Interviewees had no knowledge of any radiological production or storage areas in Building 763.

Describe any potential, likely, or known spill locations (e.g., known leaking sealed radioactive sources, leaking waste drums, potentially contaminated drains, etc.): Interviewees had no knowledge of any radioactive materials of any kind used or stored in or passing through Building 763, therefore the likelihood of a radiological spill was non-existent.

Describe methods in which spills were mitigated, if any: NA Interviewees had no knowledge of any radioactive materials of any kind used or stored in, or passing through Building 763, therefore, spill mitigation was never required.

Describe any potential, likely, or known isotopes of concern (e.g., weapons grade plutonium, uranium isotopes, pure beta emitters, mixed fission products, etc.): NA. Interviewees had no knowledge of any radioactive materials of any kind used or stored in, or passing through Building 763.

Describe any potential, likely, or known external facility contamination (e.g., stack release points, unfiltered ventilation, facility's physical location to known site releases, etc.):

NA. Interviewees had no knowledge of any radioactive materials of any kind used, stored in, or passing through Building 763.

Describe any process waste lines associated with the facility, if any (Are any abandoned? Capped?) Building 763 has no process waste lines, therefore, there are no abandoned and/or capped process waste lines. Building 763 has one storm sewer access manhole cover in the floor near the west wall (south section of the building).

Environmental Restoration Concerns

Describe any ER concerns that could affect facility characterization (e.g., IHSSs, PACs, UBCs): Interviewees had no knowledge of any ER concerns associated with Building 763. Nick Demos, ER Program, does have IHSS, PAC or UBC concerns for the soils at the Building 763 site. There are three IHSS/PACs concerning the soils/land that Building 763 is constructed on. These IHSS/PACs are 700-185, 700-194, and IHSS/PAC 700-1103.

Additional Information

Describe any additional information that may be useful during facility characterization (e.g., contaminant migration routes, waste handling operations, physical hazards, Historical Release Reports, WSRIC data, etc.): Interviewees had no knowledge of any additional information that may be useful during facility characterization. There are no WSRIC data concerning Building 763.

D&D RISS Facility Characterization Historical Site Assessment Report

References

Provide all sources of information utilized to gather data for facility history (e.g., documents, files, interviews). Attach all applicable supporting documentation.

References used were: Site SAR, HRR, IHSS/PAC/UBC Site Maps, List of Beryllium Areas, Historical and Present, B130 Asbestos Inventory Library, Building 763 Engineering Drawings, Master Listing of RCRA Units, Appendix 1 of Idle Equipment With Hazardous Materials Inventory, and Appendix 1A of Idle Equipment With Non-Hazardous Materials Inventory.

Waste Volume Estimates and Material Types Building 763

| Concrete (cu ft) | Wood (cu ft) | Metal (cu ft) | Corrugated Sheet Metal (cu ft) | Wall Board (cu ft) | ACM | Other Waste |
|---------------------|-----------------|------------------|--------------------------------------|-----------------------|---------|--|
| 6,300 | 320 | 610 | 1,050 | 0 | Unknown | Lexan® 32 cu ft Glass 3 cu ft Insulation 790 cu ft Mercury vapor lights 3 cu ft Fluorescent light fix. 52 cu ft Aluminum metal 16 cu ft |

Further Actions

Recommend any further actions, if any (e.g., characterization, decontamination, special handling, etc.):

Interviewees had no further actions or recommendations concerning the characterization of Building 763. The author of this RISS HSA Report has no further actions or recommendations concerning the characterization of Building 763.

Note:

This HSA was performed prior to SME walkdowns, and chemical and radiological characterization package preparations. Information contained in this HSA only represents a "snapshot" in time. Subsequent data may be obtained during SME walkdowns and chemical and radiological characterization package preparations, which may conflict with this report. However, this report will not be amended, and the newer data will take precedence over the data in the report. Newer Data will appear in the RLCR/PDSR.

Prepared By:

Bob Sheets

Print Name

Signature

Date

56

D&D RISS Facility Characterization Historical Site Assessment Report

Facility ID: T900C – OU-2 Office Trailer/ Surface Water Treatment
Anticipated Facility Type (1, 2, or 3): Type 1

Refer to attached site drawing for facility location.

This facility specific Historical Site Assessment (HSA) has been performed in accordance with:

D&D Characterization Protocol, RFETS MAN-077-DDCP, latest version, and

Facility Disposition Program Manual, RFETS MAN-076-FDPM, latest version

Physical Description

T900C is a 48-foot long by 8-feet wide flat bed trailer, which was enclosed by a 9-foot high tube-steel structure. The sides of the structure have five four-foot double-wide doors for adding or removing equipment from the trailer bed. There are doors on the west end and the northeast corner reached by metal steps. Insulation material in the structure walls is unknown as the doors have a wood frame attached to the perimeter of the doors and are covered with a thick textured, plastic, covering that is screwed to the frame. The underneath of the deck of the trailer is a foamed insulation material. The end panel insulation is foam insulation between aluminum sheets. Ceiling insulation could not be determined. The deck is painted diamond-plate steel. Inside the trailer on the east end there are electric panels and controls and a step down transformer for equipment that has been removed. On the south wall is a 3 ft W X 2 ½ ft D X 4-ft H hood that contains a drying oven. Exhaust for the hood is supplied by a portable air mover with a HEPA filter outside on the ground. On the south side is a circular lead shield for a counting detector on a steel table. Air conditioning is supplied by an air conditioning unit that is located on the ground at the southeast corner of the trailer. There are five liquid nitrogen dewars sitting on steel plates on the ground on the north side of the trailer.

Historical Operations

The trailer was brought on site in 1991 and located northeast of what was Guard Post 900. Vessels of granular activated carbon were installed in the trailer to remove VOCs by adsorption from surface water sites, SWS 59, 61 and 132 located in OU 2 on the hillside north of the trailer. This operation lasted from 1991 to 1995 when the vessels were removed. It remained empty until 1998 when the hood, detector shield, and gamma spectroscopy equipment was installed to be used in support of the removal of Trench 1. Gamma spectroscopy procedures were also performed on ER samples from various sites around the plant. Gamma spectroscopy operations were concluded in 2000 and the gamma detection equipment was removed from the trailer. The hood and the detector shield were left in the trailer. Also in the trailer are three tables and chairs that were used to support gamma spectroscopy operations.

Current Operational Status

Currently there are no operations being conducted in the trailer. After the closure of Trench One Operations all the equipment used for gamma spectroscopy was removed with the exception of the lead-shielded detection chamber. Other remaining equipment in the trailer includes, three tables, chairs, the hood with a drying oven and the electrical controls and switchgear.

Contaminants of Concern

Asbestos

Describe any potential, likely, or known sources of Asbestos:

The trailer is not posted as being an ACM area.

D&D RISS Facility Characterization Historical Site Assessment Report

Beryllium (Be)

Describe any potential, likely, or known Be production or storage locations:
The trailer is not on the list of known Be containing areas.

Summarize any recent Be sampling results:
None.

Lead

Describe any potential, likely, or known sources of Lead (e.g., paint, shielding, etc.):
The only known source of lead is the commercial-built detector shield that is in the trailer.

RCRA/CERCLA Constituents

Describe any potential, likely, or known sources of RCRA/CERCLA constituents (e.g., chemical storage, waste storage, processes):

VOC contaminated surface water was treated in the trailer. Trench One could have contained RCRA/CERCLA constituents.

Describe any potential, likely, or known spill locations (and sources, if any):
No known spill.

Describe methods in which spills were mitigated, if any:
N/A

PCBs

Describe any potential, likely, or known sources of PCBs (e.g., light ballasts, paints, equipment, etc.):
The fluorescent light ballast may contain PCB. The electrical switchgear and transformer are not labeled as containing PCBs.

Describe any potential, likely, or known spill locations (and sources, if any):
No known spill.

Describe methods in which spills were mitigated, if any:
N/A.

D&D RISS Facility Characterization Historical Site Assessment Report

Radiological Contaminants

Describe any potential, likely, or known radiological production or storage locations:

Surface water treated had very low levels of radioactivity prior to the addition of pre-treatment, which occurred in other trailers. Trench 1 materials were radiologically contaminated. The trailer has no radioactive postings on it.

Describe any potential, likely, or known spill locations (e.g., known leaking sealed radioactive sources, leaking waste drums, potentially contaminated drains, etc.):

None.

Describe methods in which spills were mitigated, if any:

N/A.

Describe any potential, likely, or known isotopes of concern (e.g., weapons grade plutonium, uranium isotopes, pure beta emitters, mixed fission products, etc.):

The trailer analyzed samples that contained depleted uranium. Various gamma sources were also stored in the trailer.

Describe any potential, likely, or known external facility contamination (e.g., stack release points, unfiltered ventilation, facility's physical location to known site releases, etc.):

Environmental Restoration Concerns

Describe any ER concerns that could affect facility characterization (e.g., IHSSs, PACs, UBCs):

The facility does not sit or is listed as being on an IHSSs, PACs, or UBCs.

None.

Additional Information

Describe any additional information that may be useful during facility characterization (e.g., contaminant migration routes, waste handling operations, physical hazards, Historical Release Reports, WSRIC data, etc.):

The facility is not listed in the Historical Release Reports and has no WSRIC.

References

Provide all sources of information utilized to gather data for facility history (e.g., documents, files, interviews). Attach all applicable supporting documentation:

Site IHSS, PAC, and UBC map; HRR list; and WSRIC list; and interviews.

Waste Volume Estimates and Material Types

| Concrete (cu ft) | Wood (cu ft) | Metal (cu ft) | Corrugated Sheet Metal (cu ft) | Wall Board (cu ft) | ACM | Other Waste |
|---------------------|-----------------|------------------|--------------------------------------|-----------------------|-----|-------------|
| | | | | | | |

NOTE: This trailer is expected to be returned to commerce.

D&D RISS Facility Characterization Historical Site Assessment Report

Further Actions

Recommend any further actions, if any (e.g., characterization, decontamination, special handling, etc.):
Start the RLC/PDS process.

Note:

This HSA was performed prior to SME walkdowns, and chemical and radiological characterization package preparations. Information contained in this HSA only represents a "snapshot" in time. Subsequent data may be obtained during SME walkdowns and chemical and radiological characterization package preparations which may conflict with this report. However, this report will not be amended and the newer data will take precedence over the data in the report.

Prepared By:

Dean Burton

Print Name

Signature

Date

ATTACHMENT C

Radiological Data Summaries and Survey Maps

Summary of Radiological Survey Data for Group 10 Facilities

| | | Removable Activity (RA) | | | | Total Surface Activity (TSA) | | | |
|---|--------------------------------|--|------|---------------------------------------|------|--|------|------------------------------------|-------|
| | | Alpha (dpm/100 cm ²) | | Beta (dpm/100 cm ²) | | Alpha (dpm/100 cm ²) | | Beta (dpm/100 cm ²) | |
| | | DCGL ¹ | | 1000 | | 100 | | 5000 | |
| | | No. of Survey Measurements | | Min. | Max. | Min. | Max. | Min. | Max. |
| B125 Interior and Exterior (Survey Units G10004 & G10005) | 47 random 45 biased 8 QC | -0.9 | 11.8 | -30.0 | 44.0 | -13.0 | 61.5 | -804.0 | 688.2 |
| B763 Interior and Exterior (Survey Units G10001 & G10002) | 31 random 4 QC | -0.9 | 3.9 | -26.0 | 42.0 | -9.6 | 94.5 | -719.1 | 814.2 |
| T900C Interior and Exterior (Survey Unit G10003) | 15 random 2 QC | -0.9 | 3.6 | -32.0 | 38.0 | -7.7 | 65.1 | -521.4 | 157.5 |

¹DCGL – Derived Concentration Guideline Level

Original survey data sheets and analytical data are contained in the Group 10 RLC files, including chain of custody and QC documentation.

TSA Alpha


G10001

10/9/01

| | | | | | | |
|------------|-----|------|------|------------------------|----------|--------------|
| | | | | Instrument: | 1 394 | 2 1425 QC |
| std. Dev.: | 6.7 | max: | 14.7 | Ave. Inst. background: | 2.8 | 3.0 cpm |
| mean: | 3.9 | min: | -9.6 | Instrument efficiency: | 21.80% | 21.50% |
| median: | 2.4 | | | Instrument MDA: | 48 | 48 dpm |

| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|---|
| 1 | 763 interior | 5.3 | 2.0 | 11.5 | 100 |
| 2 | 763 interior | 3.3 | 4.0 | 2.4 | 100 |
| 3 | 763 interior | 4.0 | 0.7 | 5.6 | 100 |
| 4 | 763 interior | 6.0 | 2.0 | 14.7 | 100 |
| 5 | 763 interior | 6.0 | 4.0 | 14.7 | 100 |
| 6 | 763 interior | 0.7 | 2.0 | -9.6 | 100 |
| 7 | 763 interior | 2.7 | 3.3 | -0.4 | 100 |
| 8 | 763 interior | 2.7 | 1.3 | -0.4 | 100 |
| 9 | 763 interior | 4.3 | 1.3 | 6.9 | 100 |
| 10 | 763 interior | 3.3 | 2.7 | 2.4 | 100 |
| 11 | 763 interior | 3.3 | 2.0 | 2.4 | 100 |
| 12 | 763 interior | 3.3 | 6.0 | 2.4 | 100 |
| 13 | 763 interior | 4.7 | 3.3 | 8.8 | 100 |
| 14 | 763 interior | 1.3 | 2.0 | -6.8 | 100 |
| 15 | 763 interior | 3.3 | 4.7 | 2.4 | 100 |
| 16 | 763 interior | 4.0 | 3.3 | 5.6 | 100 |
| 4 QC | 763 interior | 6.7 | 2.0 | 17.2 | 100 |
| 11 QC | 763 interior | 5.3 | 4.0 | 10.7 | 100 |

Unit Measurements



Total Alpha Activity (dpm/100cm²)
 Total Alpha DCGL (dpm/100cm²)

33

Removable Activity - Alpha


G10001

10/9/01

| | | | | |
|---------------------|-----|-------------------------------|---|------------------------------------|
| | | | Instrument: ¹ 966 ² 770 | |
| standard deviation: | 1.4 | max: | 3.6 | Instrument background: 0.3 0.2 cpm |
| mean: | 0.5 | min: | -0.9 | Instrument efficiency: 33.0% 33.0% |
| median: | 0.0 | Instrument MDA: 10.0 10.0 dpm | | |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable α DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|---|
| 1 | 763 interior | 1.0 | 0.3 | 2.1 | 20 |
| 2 | 763 interior | 0.5 | 0.2 | 0.9 | 20 |
| 3 | 763 interior | 1.0 | 0.3 | 2.1 | 20 |
| 4 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 5 | 763 interior | 1.0 | 0.3 | 2.1 | 20 |
| 6 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 7 | 763 interior | 0.0 | 0.3 | -0.9 | 20 |
| 8 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 9 | 763 interior | 1.5 | 0.3 | 3.6 | 20 |
| 10 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 11 | 763 interior | 0.0 | 0.3 | -0.9 | 20 |
| 12 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 13 | 763 interior | 0.5 | 0.3 | 0.6 | 20 |
| 14 | 763 interior | 0.0 | 0.2 | -0.6 | 20 |
| 15 | 763 interior | 0.5 | 0.3 | 0.6 | 20 |
| 16 | 763 interior | 0.5 | 0.2 | 0.9 | 20 |

Unit Measurements



TSA Beta-Gamma


G10001

10/9/01

| | | | | |
|------------|-------|-------------|---|-----------------|
| | | | Instrument: ¹ 394 ² 1425 QC | |
| std. Dev.: | 459.8 | max: 814.2 | Ave. Inst. background: | 639.9 639.9 cpm |
| mean: | 318.6 | min: -719.1 | Instrument efficiency: | 28.50% 31.10% |
| median: | 556.3 | | Instrument MDA: | 48 48 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Total β-γ DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|--|
| 1 | 763 interior | 872 | 701 | 814.2 | 5000 |
| 2 | 763 interior | 672 | 685 | 112.5 | 5000 |
| 3 | 763 interior | 653 | 550 | 45.8 | 5000 |
| 4 | 763 interior | 848 | 700 | 730.0 | 5000 |
| 5 | 763 interior | 645 | 532 | 17.7 | 5000 |
| 6 | 763 interior | 796 | 740 | 547.6 | 5000 |
| 7 | 763 interior | 823 | 613 | 642.3 | 5000 |
| 8 | 763 interior | 435 | 503 | -719.1 | 5000 |
| 9 | 763 interior | 843 | 706 | 712.5 | 5000 |
| 10 | 763 interior | 828 | 668 | 659.8 | 5000 |
| 11 | 763 interior | 801 | 662 | 565.1 | 5000 |
| 12 | 763 interior | 641 | 488 | 3.7 | 5000 |
| 13 | 763 interior | 846 | 678 | 723.0 | 5000 |
| 14 | 763 interior | 527 | 582 | -396.3 | 5000 |
| 15 | 763 interior | 823 | 667 | 642.3 | 5000 |
| 16 | 763 interior | 639 | 528 | -3.3 | 5000 |
| 4 QC | 763 interior | 957 | 751 | 1019.5 | 5000 |
| 11 QC | 763 interior | 783 | 765 | 460.0 | 5000 |

Unit Measurements




Removable Activity - Beta-Gamma

G10001

10/9/01

| | | | | |
|---------------------|------|-------------------------------|---|--------------------------------------|
| | | | Instrument: ³ 905 ⁴ 700 | |
| standard deviation: | 18.8 | max: | 40.0 | Instrument background: 35.0 32.0 cpm |
| mean: | 13.8 | min: | -14.0 | Instrument efficiency: 25.0% 25.0% |
| median: | 16.0 | Instrument MDA: 41.9 40.2 dpm | | |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable β DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|---|
| 1 | 763 interior | 37.5 | 35.0 | 10.0 | 1000 |
| 2 | 763 interior | 28.5 | 32.0 | -14.0 | 1000 |
| 3 | 763 interior | 45.0 | 35.0 | 40.0 | 1000 |
| 4 | 763 interior | 29.0 | 32.0 | -12.0 | 1000 |
| 5 | 763 interior | 44.0 | 35.0 | 36.0 | 1000 |
| 6 | 763 interior | 37.0 | 32.0 | 20.0 | 1000 |
| 7 | 763 interior | 44.5 | 35.0 | 38.0 | 1000 |
| 8 | 763 interior | 36.5 | 32.0 | 18.0 | 1000 |
| 9 | 763 interior | 38.5 | 35.0 | 14.0 | 1000 |
| 10 | 763 interior | 30.0 | 32.0 | -8.0 | 1000 |
| 11 | 763 interior | 44.5 | 35.0 | 38.0 | 1000 |
| 12 | 763 interior | 28.5 | 32.0 | -14.0 | 1000 |
| 13 | 763 interior | 40.5 | 35.0 | 22.0 | 1000 |
| 14 | 763 interior | 34.0 | 32.0 | 8.0 | 1000 |
| 15 | 763 interior | 36.5 | 35.0 | 6.0 | 1000 |
| 16 | 763 interior | 36.5 | 32.0 | 18.0 | 1000 |



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area:

Survey Unit:

Classification: 3

Building: 763



Survey Unit Description: Interior

Total Floor Area: NA

Total Area: 1042 sq. m

Grid Size: N/A

SURVEY UNIT - MAP 1 OF 1



Scan Areas

SURVEY MAP LEGEND

- Smear & TSC Location
- Smear, TSC & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

TSA Alpha

G10002


10/8/01

| | | | | | | | |
|------------|------|------|------|------------------------|-----------|----------|--------------|
| | | | | Instrument: | 1 3114 | 2 394 | 3 1425 QC |
| std. Dev.: | 26.3 | max: | 94.5 | Ave. Inst. background: | 2.7 | 2.7 | 3.7 cpm |
| mean: | 45.4 | min: | 5.9 | Instrument efficiency: | 22.00% | 21.80% | 21.50% |
| median: | 42.7 | | | Instrument MDA: | 48 | 48 | 48 dpm |

| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|---|
| 1 | 763 Exterior | 23.3 | 0.7 | 94.5 | 100 |
| 2* | 763 Exterior | 12.0 | 1.3 | 42.7 | 100 |
| 3 | 763 Exterior | 11.3 | 5.3 | 39.1 | 100 |
| 4 | 763 Exterior | 12.7 | 1.3 | 45.9 | 100 |
| 5 | 763 Exterior | 4.7 | 1.3 | 9.2 | 100 |
| 6 | 763 Exterior | 14.0 | 1.3 | 51.8 | 100 |
| 7 | 763 Exterior | 8.0 | 3.3 | 24.1 | 100 |
| 8 | 763 Exterior | 6.7 | 5.3 | 18.2 | 100 |
| 9* | 763 Exterior | 16.0 | 4.0 | 60.5 | 100 |
| 10* | 763 Exterior | 20.0 | 2.0 | 78.6 | 100 |
| 11 | 763 Exterior | 16.7 | 2.7 | 63.6 | 100 |
| 12 | 763 Exterior | 4.0 | 5.3 | 5.9 | 100 |
| 13 | 763 Exterior | 10.0 | 0.7 | 33.5 | 100 |
| 14* | 763 Exterior | 20.0 | 1.3 | 79.4 | 100 |
| 15 | 763 Exterior | 10.0 | 4.7 | 33.5 | 100 |
| 8 QC | 763 Exterior | 8.7 | 1.3 | 23.5 | 100 |
| 13 QC | 763 Exterior | 6.7 | 6.0 | 14.2 | 100 |

* Locations are investigative recounts.

Unit Measurements



3p


TSA Beta-Gamma

G10002

1/0/00

| | | | | | | |
|------------|-------|-------------|------------------------|-----------|----------|--------------|
| | | | Instrument: | 1 3114 | 2 394 | 3 1425 QC |
| std. Dev.: | 218.7 | max: 382.0 | Ave. Inst. background: | 560.2 | 560.2 | 654.0 cpm |
| mean: | 18.1 | min: -400.8 | Instrument efficiency: | 32.40% | 28.50% | 31.10% |
| median: | 9.7 | | Instrument MDA: | 253 | 263 | 260 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Total β-γ DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|---|
| 1 | 763 Exterior | 585 | 482 | 86.9 | 5000 |
| 2* | 763 Exterior | 493 | 487 | -235.9 | 5000 |
| 3 | 763 Exterior | 657 | 769 | 298.7 | 5000 |
| 4 | 763 Exterior | 514 | 461 | -162.2 | 5000 |
| 5 | 763 Exterior | 557 | 492 | -11.4 | 5000 |
| 6 | 763 Exterior | 551 | 546 | -32.4 | 5000 |
| 7 | 763 Exterior | 599 | 469 | 119.6 | 5000 |
| 8 | 763 Exterior | 684 | 725 | 382.0 | 5000 |
| 9* | 763 Exterior | 513 | 443 | -145.8 | 5000 |
| 10* | 763 Exterior | 501 | 479 | -182.8 | 5000 |
| 11 | 763 Exterior | 583 | 557 | 70.3 | 5000 |
| 12 | 763 Exterior | 633 | 764 | 224.6 | 5000 |
| 13 | 763 Exterior | 446 | 446 | -400.8 | 5000 |
| 14* | 763 Exterior | 563 | 540 | 9.7 | 5000 |
| 15 | 763 Exterior | 632 | 556 | 251.8 | 5000 |
| 8 QC | 763 Exterior | 717 | 717 | 202.6 | 5000 |
| 13 QC | 763 Exterior | 591 | 591 | -202.6 | 5000 |



39

Removable Activity - Alpha


G10002

10/8/01

| | | | | | | |
|---------------------|-----|------|------|------------------------|----------|----------|
| | | | | Instrument: | 1 966 | 2 770 |
| standard deviation: | 1.2 | max: | 3.9 | Instrument background: | 0.1 | 0.2 cpm |
| mean: | 1.3 | min: | -0.6 | Instrument efficiency: | 33.0% | 33.0% |
| median: | 1.2 | | | Instrument MDA: | 10.0 | 10.0 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable α DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|--|
| 1 | 763 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 2 | 763 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 3 | 763 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 4 | 763 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 5 | 763 Exterior | 0.5 | 0.2 | 0.9 | 20 |
| 6 | 763 Exterior | 0.5 | 0.2 | 0.9 | 20 |
| 7 | 763 Exterior | 1.0 | 0.2 | 2.4 | 20 |
| 8 | 763 Exterior | 1.0 | 0.1 | 2.7 | 20 |
| 9 | 763 Exterior | 1.0 | 0.2 | 2.4 | 20 |
| 10 | 763 Exterior | 1.5 | 0.2 | 3.9 | 20 |
| 11 | 763 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 12 | 763 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 13 | 763 Exterior | 0.5 | 0.2 | 0.9 | 20 |
| 14 | 763 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 15 | 763 Exterior | 0.0 | 0.2 | -0.6 | 20 |

Unit Measurements



Total Activity (dpm/100cm²)
 Removable α DCGL (dpm/100cm²)

40

Removable Activity - Beta-Gamma



G10002

10/8/01

| | | | | |
|---------------------|------|-------------------------------|---|--------------------------------------|
| | | | Instrument: ³ 905 ⁴ 700 | |
| standard deviation: | 17.9 | max: | 42.0 | Instrument background: 40.0 32.0 cpm |
| mean: | 1.9 | min: | -26.0 | Instrument efficiency: 25.0% 25.0% |
| median: | 4.0 | Instrument MDA: 44.5 40.2 dpm | | |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable β DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|---|
| 1 | 763 Exterior | 38.0 | 40.0 | -8.0 | 1000 |
| 2 | 763 Exterior | 42.0 | 40.0 | 8.0 | 1000 |
| 3 | 763 Exterior | 46.0 | 40.0 | 24.0 | 1000 |
| 4 | 763 Exterior | 33.5 | 40.0 | -26.0 | 1000 |
| 5 | 763 Exterior | 27.5 | 32.0 | -18.0 | 1000 |
| 6 | 763 Exterior | 27.0 | 32.0 | -20.0 | 1000 |
| 7 | 763 Exterior | 42.5 | 32.0 | 42.0 | 1000 |
| 8 | 763 Exterior | 41.5 | 40.0 | 6.0 | 1000 |
| 9 | 763 Exterior | 36.0 | 32.0 | 16.0 | 1000 |
| 10 | 763 Exterior | 32.5 | 32.0 | 2.0 | 1000 |
| 11 | 763 Exterior | 37.0 | 40.0 | -12.0 | 1000 |
| 12 | 763 Exterior | 38.0 | 40.0 | -8.0 | 1000 |
| 13 | 763 Exterior | 34.0 | 32.0 | 8.0 | 1000 |
| 14 | 763 Exterior | 41.0 | 40.0 | 4.0 | 1000 |
| 15 | 763 Exterior | 34.5 | 32.0 | 10.0 | 1000 |

Unit Measurements





2/1


RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: Survey Unit: Classification: 3
 Building: 763
 Survey Unit Description: Exterior
 Total Floor Area: NA Total Area: 951 sq. m Grid Size: N/A

SURVEY UNIT - MAP 1 OF 1



Scan Areas




TSA Alpha

G10003

10/19/01

| | | | | | | | |
|------------|------|------|------|------------------------|-----------|-------------|----------|
| | | | | Instrument: | 1 3114 | 2 394 QC | 3 394 |
| std. Dev.: | 20.9 | max: | 65.1 | Ave. Inst. background: | 3.0 | 2.4 cpm | 3.0 cpm |
| mean: | 23.2 | min: | -7.7 | Instrument efficiency: | 22.00% | 21.80% | 21.80% |
| median: | 22.8 | | | Instrument MDA: | 48 | 48 dpm | 48 dpm |

| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|---|
| 1 | T900C Int & Ext | 8.0 | 1.3 | 23.0 | 100 |
| 2 | T900C Int & Ext | 12.0 | 4.0 | 41.0 | 100 |
| 3 | T900C Int & Ext | 1.3 | 1.3 | -7.7 | 100 |
| 4 | T900C Int & Ext | 8.0 | 2.7 | 22.8 | 100 |
| 5 | T900C Int & Ext | 1.3 | 0.0 | -7.7 | 100 |
| 6 | T900C Int & Ext | 5.3 | 4.0 | 10.6 | 100 |
| 7 | T900C Int & Ext | 4.0 | 0.7 | 4.7 | 100 |
| 8 | T900C Int & Ext | 12.7 | 4.0 | 44.2 | 100 |
| 9 | T900C Int & Ext | 8.0 | 2.0 | 23.0 | 100 |
| 10 | T900C Int & Ext | 17.3 | 0.0 | 65.1 | 100 |
| 11 | T900C Int & Ext | 6.7 | 6.0 | 16.9 | 100 |
| 12 | T900C Int & Ext | 12.7 | 6.7 | 44.2 | 100 |
| 13 | T900C Int & Ext | 6.4 | 7.3 | 15.5 | 100 |
| 14 | T900C Int & Ext | 12.7 | 4.7 | 44.2 | 100 |
| 15 | T900C Int & Ext | 4.7 | 0.0 | 7.9 | 100 |
| 11 QC | T900C Int & Ext | 3.3 | 2.7 | 4.4 | 100 |
| 4 QC | T900C Int & Ext | 1.3 | 2.0 | -4.8 | 100 |



43

TSA Beta-Gamma

G10003


10/19/01

1 2 3

| | | | | | | | |
|------------|-------|------|--------|------------------------|--------|-----------|-----------|
| std. Dev.: | 206.1 | max: | 157.5 | Instrument: | 3114 | 394 QC | 394 |
| mean: | -23.6 | min: | -521.4 | Ave. Inst. background: | 370.7 | 347.0 cpm | 370.7 cpm |
| median: | 87.9 | | | Instrument efficiency: | 22.00% | 21.80% | 21.80% |
| | | | | Instrument MDA: | 48 | 48 dpm | 48 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Total β-γ DCGL (dpm/100cm ²) |
|-------|------------------|---|--|---|---|
| 1 | T900C Int & Ext | 313 | 308 | -264.5 | 5000 |
| 2 | T900C Int & Ext | 396 | 391 | 115.2 | 5000 |
| 3 | T900C Int & Ext | 257 | 326 | -521.4 | 5000 |
| 4 | T900C Int & Ext | 403 | 423 | 147.0 | 5000 |
| 5 | T900C Int & Ext | 405 | 423 | 157.5 | 5000 |
| 6 | T900C Int & Ext | 403 | 315 | 148.3 | 5000 |
| 7 | T900C Int & Ext | 314 | 315 | -259.9 | 5000 |
| 8 | T900C Int & Ext | 361 | 431 | -43.9 | 5000 |
| 9 | T900C Int & Ext | 323 | 325 | -218.7 | 5000 |
| 10 | T900C Int & Ext | 398 | 397 | 124.2 | 5000 |
| 11 | T900C Int & Ext | 353 | 411 | -80.3 | 5000 |
| 12 | T900C Int & Ext | 390 | 380 | 87.9 | 5000 |
| 13 | T900C Int & Ext | 402 | 371 | 142.4 | 5000 |
| 14 | T900C Int & Ext | 395 | 391 | 110.6 | 5000 |
| 15 | T900C Int & Ext | 371 | 353 | 1.5 | 5000 |
| 11 QC | T900C Int & Ext | 310 | 305 | -169.7 | 5000 |
| 4 QC | T900C Int & Ext | 386 | 389 | 178.9 | 5000 |

Unit Measurements



44


Removable Activity - Alpha

G10003

10/19/01

| | | | | |
|---------------------|-----|------|------------------------------------|------------------------------------|
| | | | Instrument: 966 770 | |
| standard deviation: | 1.4 | max: | 3.6 | |
| mean: | 1.0 | min: | -0.9 | Instrument background: 0.3 0.1 cpm |
| median: | 1.2 | | | |
| | | | Instrument efficiency: 33.0% 33.0% | |
| | | | Instrument MDA: 7.8 6.2 dpm | |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable α DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|---|
| 1 | T900C Int & Ext | 0.0 | 0.3 | -0.9 | 20 |
| 2 | T900C Int & Ext | 0.5 | 0.1 | 1.2 | 20 |
| 3 | T900C Int & Ext | 0.0 | 0.1 | -0.3 | 20 |
| 4 | T900C Int & Ext | 0.5 | 0.1 | 1.2 | 20 |
| 5 | T900C Int & Ext | 0.5 | 0.1 | 1.2 | 20 |
| 6 | T900C Int & Ext | 0.5 | 0.1 | 1.2 | 20 |
| 7 | T900C Int & Ext | 1.0 | 0.1 | 2.7 | 20 |
| 8 | T900C Int & Ext | 0.5 | 0.3 | 0.6 | 20 |
| 9 | T900C Int & Ext | 1.5 | 0.3 | 3.6 | 20 |
| 10 | T900C Int & Ext | 0.5 | 0.3 | 0.6 | 20 |
| 11 | T900C Int & Ext | 1.0 | 0.3 | 2.1 | 20 |
| 12 | T900C Int & Ext | 1.0 | 0.1 | 2.7 | 20 |
| 13 | T900C Int & Ext | 0.5 | 0.3 | 0.6 | 20 |
| 14 | T900C Int & Ext | 0.0 | 0.3 | -0.9 | 20 |
| 15 | T900C Int & Ext | 0.0 | 0.3 | -0.9 | 20 |



Removable Activity - Beta-Gamma

G10003


10/18/01

standard deviation: 19.3 max: 38.0
mean: -3.2 min: -32.0
median: -2.0

Instrument: 966 770
Instrument background: 37.0 35.0 cpm
Instrument efficiency: 25.0% 25.0%
Instrument MDA: 42.9 41.9 dpm

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable β DCGL (dpm/100cm ²) |
|----|------------------|---|-----------------------------------|---|---|
| 1 | T900C Int & Ext | 36.5 | 37.0 | -2.0 | 1000 |
| 2 | T900C Int & Ext | 31.0 | 35.0 | -16.0 | 1000 |
| 3 | T900C Int & Ext | 36.5 | 35.0 | 6.0 | 1000 |
| 4 | T900C Int & Ext | 34.5 | 35.0 | -2.0 | 1000 |
| 5 | T900C Int & Ext | 29.5 | 35.0 | -22.0 | 1000 |
| 6 | T900C Int & Ext | 33.5 | 35.0 | -6.0 | 1000 |
| 7 | T900C Int & Ext | 28.5 | 35.0 | -26.0 | 1000 |
| 8 | T900C Int & Ext | 37.5 | 37.0 | 2.0 | 1000 |
| 9 | T900C Int & Ext | 39.5 | 37.0 | 10.0 | 1000 |
| 10 | T900C Int & Ext | 29.0 | 37.0 | -32.0 | 1000 |
| 11 | T900C Int & Ext | 40.0 | 37.0 | 12.0 | 1000 |
| 12 | T900C Int & Ext | 27.5 | 35.0 | -30.0 | 1000 |
| 13 | T900C Int & Ext | 38.5 | 37.0 | 6.0 | 1000 |
| 14 | T900C Int & Ext | 40.5 | 37.0 | 14.0 | 1000 |
| 15 | T900C Int & Ext | 46.5 | 37.0 | 38.0 | 1000 |

Unit Measurements





Total Activity (dpm/100cm²)
 Removable b DCGL (dpm/100cm²)

46

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: Survey Unit: G10003 Classification: 3
 Building: T900C
 Survey Unit Description: Interior/Exterior
 Total Floor Area: 37 sq. m Total Area: 346 sq. m Grid Size: N/A

SURVEY UNIT - MAP 1 OF 1



TSA Alpha


G10004

10/30/01

| | | | | 1 | 2 | 3 | 4 | 5 | QC |
|------------|------|------|-------|------------------------|--------|--------|--------|--------|---------|
| | | | | 1425 | 394 | 394 | 1379 | 1136 | |
| std. Dev.: | 11.6 | max: | 25.1 | Ave. Inst. background: | 4.1 | 4.1 | 4.1 | 4.1 | 4.4 cpm |
| mean: | 0.3 | min: | -13.0 | Instrument efficiency: | 21.50% | 21.80% | 21.80% | 20.80% | 21.10% |
| median: | -5.1 | | | Instrument MDA: | 48 | 48 | 48 | 48 | 48 dpm |

| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------------|---|--|---|---|
| 1 | B125 Interior (random) | 2.7 | 11.3 | -6.4 | 100 |
| 2 | B125 Interior (random) | 1.3 | 4.0 | -12.8 | 100 |
| 3 | B125 Interior (random) | 2.7 | 2.7 | -6.7 | 100 |
| 4 | B125 Interior (random) | 6.7 | 2.7 | 12.6 | 100 |
| 5 | B125 Interior (random) | 1.3 | 4.7 | -12.8 | 100 |
| 6 | B125 Interior (random) | 4.7 | 4.0 | 2.9 | 100 |
| 7 | B125 Interior (random) | 2.7 | 2.0 | -6.7 | 100 |
| 8 | B125 Interior (random) | 7.3 | 6.0 | 15.4 | 100 |
| 9 | B125 Interior (random) | 2.7 | 0.7 | -6.7 | 100 |
| 10 | B125 Interior (random) | 4.7 | 4.0 | 2.8 | 100 |
| 11 | B125 Interior (random) | 2.7 | 2.7 | -6.4 | 100 |
| 12 | B125 Interior (random) | 9.3 | 3.3 | 25.1 | 100 |
| 13 | B125 Interior (random) | 3.3 | 2.0 | -3.8 | 100 |
| 14 | B125 Interior (random) | 8.0 | 4.0 | 17.9 | 100 |
| 15 | B125 Interior (random) | 6.7 | 3.3 | 12.6 | 100 |
| 16 | B125 Interior (random) | 6.7 | 8.0 | 12.6 | 100 |
| 17 | B125 Interior (random) | 2.0 | 3.3 | -10.0 | 100 |
| 18 | B125 Interior (random) | 4.7 | 7.3 | 2.8 | 100 |
| 19 | B125 Interior (random) | 6.0 | 4.7 | 9.2 | 100 |
| 20 | B125 Interior (random) | 1.3 | 2.0 | -13.0 | 100 |
| 21 | B125 Interior (random) | 1.3 | 8.0 | -12.8 | 100 |
| 22 | B125 Interior (random) | 2.0 | 4.0 | -9.6 | 100 |
| 4 QC | B125 Interior (random) | 5.3 | 4.0 | 4.5 | 100 |
| 14 QC | B125 Interior (random) | 8.0 | 4.7 | 17.3 | 100 |
| 23 | B125 Interior (biased) | 5.3 | 3.3 | 5.6 | 100 |
| 24 | B125 Interior (biased) | 0.7 | 2.7 | -15.5 | 100 |
| 25 | B125 Interior (biased) | 2.7 | 3.3 | -6.4 | 100 |
| 26 | B125 Interior (biased) | 4.7 | 4.0 | 2.8 | 100 |
| 27 | B125 Interior (biased) | 2.0 | 3.3 | -9.7 | 100 |
| 28 | B125 Interior (biased) | 0.7 | 2.0 | -15.5 | 100 |
| 29 | B125 Interior (biased) | 2.0 | 4.7 | -9.6 | 100 |
| 30 | B125 Interior (biased) | 1.3 | 1.3 | -13.0 | 100 |
| 31 | B125 Interior (biased) | 2.0 | 2.0 | -9.7 | 100 |
| 32 | B125 Interior (biased) | 2.0 | 5.3 | -9.6 | 100 |
| 33 | B125 Interior (biased) | 3.3 | 5.3 | -3.6 | 100 |
| 34 | B125 Interior (biased) | 2.0 | 2.7 | -9.6 | 100 |
| 35 | B125 Interior (biased) | 2.7 | 6.0 | -6.4 | 100 |
| 36 | B125 Interior (biased) | 2.0 | 4.7 | -9.6 | 100 |
| 37 | B125 Interior (biased) | 4.0 | 3.3 | -0.4 | 100 |
| 38 | B125 Interior (biased) | 2.7 | 4.7 | -6.4 | 100 |
| 39 | B125 Interior (biased) | 4.0 | 4.7 | -0.4 | 100 |
| 40 | B125 Interior (biased) | 5.3 | 4.7 | 5.6 | 100 |
| 41 | B125 Interior (biased) | 2.7 | 6.7 | -6.4 | 100 |
| 42 | B125 Interior (biased) | 5.3 | 3.3 | 5.6 | 100 |
| 43 | B125 Interior (biased) | 3.3 | 3.3 | -3.6 | 100 |
| 44 | B125 Interior (biased) | 4.0 | 6.7 | -0.4 | 100 |
| 45 | B125 Interior (biased) | 2.7 | 4.7 | -6.4 | 100 |
| 23 QC | B125 Interior (random) | 0.7 | 4.7 | -15.8 | 100 |
| 26 QC | B125 Interior (random) | 3.3 | 4.0 | -3.6 | 100 |

Unit Measurements



| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------------|---|--|---|---|
| 46 | B125 Interior (biased) | 5.3 | 4.0 | 5.6 | 100 |
| 47 | B125 Interior (biased) | 6.7 | 6.0 | 12.0 | 100 |
| 48 | B125 Interior (biased) | 6.7 | 8.7 | 12.0 | 100 |
| 49 | B125 Interior (biased) | 8.7 | 4.7 | 21.2 | 100 |
| 50 | B125 Interior (biased) | 5.3 | 10.0 | 5.6 | 100 |
| 51 | B125 Interior (biased) | 6.7 | 4.0 | 12.0 | 100 |
| 52 | B125 Interior (biased) | 3.3 | 7.3 | -3.6 | 100 |
| 53 | B125 Interior (biased) | 7.3 | 3.3 | 14.7 | 100 |
| 54 | B125 Interior (biased) | 3.3 | 2.0 | -3.6 | 100 |
| 55 | B125 Interior (biased) | 2.0 | 2.7 | -9.6 | 100 |
| 56 | B125 Interior (biased) | 2.0 | 4.0 | -10.0 | 100 |
| 57 | B125 Interior (biased) | 0.7 | 2.0 | -15.5 | 100 |
| 58 | B125 Interior (biased) | 2.0 | 2.7 | -9.6 | 100 |
| 59 | B125 Interior (biased) | 1.3 | 0.7 | -13.4 | 100 |
| 60 | B125 Interior (biased) | 6.0 | 3.3 | 9.2 | 100 |
| 61 | B125 Interior (biased) | 2.7 | 2.7 | -6.7 | 100 |
| 62 | B125 Interior (biased) | 4.7 | 1.3 | 2.9 | 100 |
| 63 | B125 Interior (biased) | 2.7 | 1.3 | -6.7 | 100 |
| 64 | B125 Interior (biased) | 4.0 | 2.7 | -0.4 | 100 |
| 65 | B125 Interior (biased) | 2.7 | 2.0 | -6.7 | 100 |
| 66 | B125 Interior (biased) | 4.0 | 3.3 | -0.4 | 100 |
| 67 | B125 Interior (biased) | 7.3 | 4.0 | 15.4 | 100 |
| 68 | B125 Interior (biased) | 8.0 | 6.0 | 17.9 | 100 |
| 69 | B125 Interior (biased) | 2.0 | 6.0 | -9.6 | 100 |
| 47 QC | B125 Interior (biased) | 4.7 | 4.7 | 2.9 | 100 |
| 46 QC | B125 Interior (biased) | 4.0 | 4.0 | -0.4 | 100 |

48


TSA Beta-Gamma

G10004

10/30/01

| | | | | 1 | 2 | 3 | 4 | 5 QC |
|------------|--------|------|-------------|------------------------|--------|--------|--------|-----------|
| | | | Instrument: | 1425 | 394 | 394 | 1379 | 1136 |
| std. Dev.: | 421.1 | max: | 688.2 | Ave. Inst. background: | 597.5 | 597.5 | 597.5 | 600.5 cpm |
| mean: | -172.1 | min: | -804.0 | Instrument efficiency: | 31.10% | 28.50% | 28.50% | 31.90% |
| median: | -213.1 | | | Instrument MDA: | 261 | 265 | 265 | 243 |
| | | | | | | | 237 | dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Total β - γ DCGL (dpm/100cm ²) |
|-------|------------------------|---|--|---|--|
| 1 | B125 Interior (random) | 449 | 445 | -520.9 | 5000 |
| 2 | B125 Interior (random) | 429 | 427 | -591.1 | 5000 |
| 3 | B125 Interior (random) | 483 | 641 | -358.8 | 5000 |
| 4 | B125 Interior (random) | 380 | 407 | -681.7 | 5000 |
| 5 | B125 Interior (random) | 443 | 449 | -542.0 | 5000 |
| 6 | B125 Interior (random) | 529 | 659 | -214.6 | 5000 |
| 7 | B125 Interior (random) | 563 | 623 | -108.0 | 5000 |
| 8 | B125 Interior (random) | 385 | 471 | -666.0 | 5000 |
| 9 | B125 Interior (random) | 646 | 609 | 152.2 | 5000 |
| 10 | B125 Interior (random) | 725 | 685 | 410.1 | 5000 |
| 11 | B125 Interior (random) | 627 | 613 | 103.6 | 5000 |
| 12 | B125 Interior (random) | 817 | 577 | 688.2 | 5000 |
| 13 | B125 Interior (random) | 565 | 657 | -101.8 | 5000 |
| 14 | B125 Interior (random) | 772 | 629 | 612.4 | 5000 |
| 15 | B125 Interior (random) | 469 | 516 | -402.7 | 5000 |
| 16 | B125 Interior (random) | 485 | 473 | -352.6 | 5000 |
| 17 | B125 Interior (random) | 530 | 458 | -211.5 | 5000 |
| 18 | B125 Interior (random) | 445 | 420 | -535.0 | 5000 |
| 19 | B125 Interior (random) | 341 | 520 | -804.0 | 5000 |
| 20 | B125 Interior (random) | 711 | 721 | 365.1 | 5000 |
| 21 | B125 Interior (random) | 590 | 618 | -26.2 | 5000 |
| 22 | B125 Interior (random) | 597 | 586 | -1.6 | 5000 |
| 4 QC | B125 Interior (random) | 406 | 539 | -613.6 | 5000 |
| 14 QC | B125 Interior (random) | 849 | 662 | 783.9 | 5000 |
| 23 | B125 Interior (biased) | 643 | 591 | 159.8 | 5000 |
| 24 | B125 Interior (biased) | 654 | 614 | 198.4 | 5000 |
| 25 | B125 Interior (biased) | 642 | 617 | 156.3 | 5000 |
| 26 | B125 Interior (biased) | 749 | 675 | 487.3 | 5000 |
| 27 | B125 Interior (biased) | 731 | 700 | 429.4 | 5000 |
| 28 | B125 Interior (biased) | 615 | 607 | 61.5 | 5000 |
| 29 | B125 Interior (biased) | 602 | 597 | 15.9 | 5000 |
| 30 | B125 Interior (biased) | 719 | 683 | 390.8 | 5000 |
| 31 | B125 Interior (biased) | 764 | 680 | 535.5 | 5000 |
| 32 | B125 Interior (biased) | 610 | 603 | 44.0 | 5000 |
| 33 | B125 Interior (biased) | 598 | 625 | 1.9 | 5000 |
| 34 | B125 Interior (biased) | 783 | 612 | 651.0 | 5000 |
| 35 | B125 Interior (biased) | 628 | 590 | 107.1 | 5000 |
| 36 | B125 Interior (biased) | 622 | 625 | 86.1 | 5000 |
| 37 | B125 Interior (biased) | 619 | 582 | 75.6 | 5000 |
| 38 | B125 Interior (biased) | 625 | 619 | 96.6 | 5000 |
| 39 | B125 Interior (biased) | 637 | 576 | 138.7 | 5000 |
| 40 | B125 Interior (biased) | 589 | 631 | -29.7 | 5000 |
| 41 | B125 Interior (biased) | 600 | 577 | 8.9 | 5000 |
| 42 | B125 Interior (biased) | 615 | 633 | 61.5 | 5000 |
| 43 | B125 Interior (biased) | 613 | 553 | 54.5 | 5000 |
| 44 | B125 Interior (biased) | 634 | 559 | 128.2 | 5000 |
| 45 | B125 Interior (biased) | 681 | 620 | 293.1 | 5000 |
| 23 QC | B125 Interior (random) | 735 | 679 | 442.2 | 5000 |
| 26 QC | B125 Interior (random) | 669 | 566 | 251.0 | 5000 |



| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|------------------------|---|--|---|---|
| 46 | B125 Interior (biased) | 711 | 630 | 398.4 | 5000 |
| 47 | B125 Interior (biased) | 601 | 569 | 12.4 | 5000 |
| 48 | B125 Interior (biased) | 591 | 535 | -22.7 | 5000 |
| 49 | B125 Interior (biased) | 629 | 567 | 110.7 | 5000 |
| 50 | B125 Interior (biased) | 574 | 596 | -82.3 | 5000 |
| 51 | B125 Interior (biased) | 784 | 589 | 654.5 | 5000 |
| 52 | B125 Interior (biased) | 609 | 596 | 40.5 | 5000 |
| 53 | B125 Interior (biased) | 601 | 548 | 12.4 | 5000 |
| 54 | B125 Interior (biased) | 623 | 579 | 89.6 | 5000 |
| 55 | B125 Interior (biased) | 530 | 481 | -236.7 | 5000 |
| 56 | B125 Interior (biased) | 593 | 535 | -14.0 | 5000 |
| 57 | B125 Interior (biased) | 527 | 513 | -247.2 | 5000 |
| 58 | B125 Interior (biased) | 606 | 570 | 30.0 | 5000 |
| 59 | B125 Interior (biased) | 639 | 626 | 130.2 | 5000 |
| 60 | B125 Interior (biased) | 920 | 698 | 1011.1 | 5000 |
| 61 | B125 Interior (biased) | 680 | 637 | 258.7 | 5000 |
| 62 | B125 Interior (biased) | 863 | 683 | 832.4 | 5000 |
| 63 | B125 Interior (biased) | 805 | 675 | 650.6 | 5000 |
| 64 | B125 Interior (biased) | 897 | 729 | 939.0 | 5000 |
| 65 | B125 Interior (biased) | 811 | 793 | 669.4 | 5000 |
| 66 | B125 Interior (biased) | 962 | 741 | 1142.7 | 5000 |
| 67 | B125 Interior (biased) | 959 | 791 | 1133.3 | 5000 |
| 68 | B125 Interior (biased) | 590 | 572 | -26.2 | 5000 |
| 69 | B125 Interior (biased) | 709 | 599 | 391.4 | 5000 |
| 47 QC | B125 Interior (biased) | 713 | 667 | 362.2 | 5000 |
| 46 QC | B125 Interior (biased) | 705 | 658 | 337.1 | 5000 |

49


Removable Alpha

G10004

10/24/01

| | | | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-------------|------|-----------------|------|------------------------|---|---|---|--------|--------|--------|---------|
| Instrument: | | | | | | | | 966 | 770 | 767 | 851 |
| std. Dev.: | 1.2 | max: | 2.7 | Ave. Inst. background: | | | | 0.2 | 0.3 | 0.1 | 0.3 cpm |
| mean: | -0.2 | min: | -0.9 | Instrument efficiency: | | | | 33.00% | 33.00% | 33.00% | 33.00% |
| median: | -0.8 | Instrument MDA: | | | | | | 7.1 | 7.8 | 6.2 | 7.8 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Inst. Bkgd (cpm/100cm ²) | Rem. Alpha Activity (dpm/100cm ²) | Rem. Alpha DCGL (dpm/100cm ²) |
|----|------------------------|---|---|--|--|
| 1 | B125 Interior (random) | 0.0 | 0.1 | -0.3 | 20 |
| 2 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 3 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 4 | B125 Interior (random) | 0.0 | 0.2 | -0.6 | 20 |
| 5 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 6 | B125 Interior (random) | 1.0 | 0.2 | 2.4 | 20 |
| 7 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 8 | B125 Interior (random) | 0.5 | 0.3 | 0.6 | 20 |
| 9 | B125 Interior (random) | 0.0 | 0.1 | -0.3 | 20 |
| 10 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 11 | B125 Interior (random) | 0.5 | 0.3 | 0.6 | 20 |
| 12 | B125 Interior (random) | 0.0 | 0.1 | -0.3 | 20 |
| 13 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 14 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 15 | B125 Interior (random) | 1.0 | 0.1 | 2.7 | 20 |
| 16 | B125 Interior (random) | 0.0 | 0.2 | -0.6 | 20 |
| 17 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 18 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 19 | B125 Interior (random) | 0.0 | 0.1 | -0.3 | 20 |
| 20 | B125 Interior (random) | 1.0 | 0.2 | 2.4 | 20 |
| 21 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 22 | B125 Interior (random) | 0.0 | 0.3 | -0.9 | 20 |
| 23 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 24 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 25 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 26 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 27 | B125 Interior (biased) | 0.5 | 0.1 | 1.2 | 20 |
| 28 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 29 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 30 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 31 | B125 Interior (biased) | 0.5 | 0.2 | 0.9 | 20 |
| 32 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 33 | B125 Interior (biased) | 0.5 | 0.1 | 1.2 | 20 |
| 34 | B125 Interior (biased) | 0.5 | 0.3 | 0.6 | 20 |
| 35 | B125 Interior (biased) | 0.5 | 0.3 | 0.6 | 20 |
| 36 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 37 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 38 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 39 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 40 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 41 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 42 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 43 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 44 | B125 Interior (biased) | 0.5 | 0.1 | 1.2 | 20 |
| 45 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 46 | B125 Interior (biased) | 1.0 | 0.2 | 2.4 | 20 |



| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|----|------------------------|---|--|---|---|
| 47 | B125 Interior (biased) | 0.5 | 0.3 | 0.6 | 20 |
| 48 | B125 Interior (biased) | 0.5 | 0.2 | 0.9 | 20 |
| 49 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 50 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 51 | B125 Interior (biased) | 1.5 | 0.2 | 3.9 | 20 |
| 52 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 53 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 54 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 55 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 56 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 57 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 58 | B125 Interior (biased) | 0.5 | 0.3 | 0.6 | 20 |
| 59 | B125 Interior (biased) | 0.5 | 0.2 | 0.9 | 20 |
| 60 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 61 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 62 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 63 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 64 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 65 | B125 Interior (biased) | 0.0 | 0.1 | -0.3 | 20 |
| 66 | B125 Interior (biased) | 0.0 | 0.3 | -0.9 | 20 |
| 67 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 68 | B125 Interior (biased) | 0.0 | 0.2 | -0.6 | 20 |
| 69 | B125 Interior (biased) | 0.5 | 0.1 | 1.2 | 20 |


Removable Beta-Gamma

G10004

10/24/01

| | | | | Instrument: | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | |
|------------|------|------|-------|------------------------|--------|--------|--------|--------|---|---|---|---|-------------------|-----|
| std. Dev.: | 17.3 | max: | 40.0 | Inst. background: | 835 | 911 | 905 | 700 | | | | | | |
| mean: | -2.3 | min: | -30.0 | Instrument efficiency: | 36.0 | 36.0 | 41.0 | 35.0 | | | | | Alpha Instruments | cpm |
| median: | -4.0 | | | Instrument MDA: | 25.00% | 25.00% | 25.00% | 25.00% | | | | | | dpm |
| | | | | | 42.4 | 42.4 | 44.9 | 41.9 | | | | | | |

| | Surface Location | Total Counts (cpm/100cm ²) | Inst. Bkgd (cpm/100cm ²) | Rem. Activity (dpm/100cm ²) | Rem. b - g DCGL (dpm/100cm ²) |
|----|------------------------|---|---|--|---|
| 1 | B125 Interior (random) | 38.5 | 35.0 | 14.0 | 1000 |
| 2 | B125 Interior (random) | 29.0 | 35.0 | -24.0 | 1000 |
| 3 | B125 Interior (random) | 38.0 | 41.0 | -12.0 | 1000 |
| 4 | B125 Interior (random) | 40.0 | 36.0 | 16.0 | 1000 |
| 5 | B125 Interior (random) | 36.5 | 35.0 | 6.0 | 1000 |
| 6 | B125 Interior (random) | 34.5 | 36.0 | -6.0 | 1000 |
| 7 | B125 Interior (random) | 35.0 | 36.0 | -4.0 | 1000 |
| 8 | B125 Interior (random) | 34.5 | 35.0 | -2.0 | 1000 |
| 9 | B125 Interior (random) | 45.0 | 41.0 | 16.0 | 1000 |
| 10 | B125 Interior (random) | 37.0 | 36.0 | 4.0 | 1000 |
| 11 | B125 Interior (random) | 40.5 | 36.0 | 18.0 | 1000 |
| 12 | B125 Interior (random) | 33.5 | 41.0 | -30.0 | 1000 |
| 13 | B125 Interior (random) | 37.5 | 35.0 | 10.0 | 1000 |
| 14 | B125 Interior (random) | 35.0 | 36.0 | -4.0 | 1000 |
| 15 | B125 Interior (random) | 35.5 | 41.0 | -22.0 | 1000 |
| 16 | B125 Interior (random) | 35.0 | 36.0 | -4.0 | 1000 |
| 17 | B125 Interior (random) | 36.0 | 36.0 | 0.0 | 1000 |
| 18 | B125 Interior (random) | 31.5 | 36.0 | -18.0 | 1000 |
| 19 | B125 Interior (random) | 39.5 | 41.0 | -6.0 | 1000 |
| 20 | B125 Interior (random) | 46.0 | 36.0 | 40.0 | 1000 |
| 21 | B125 Interior (random) | 32.0 | 35.0 | -12.0 | 1000 |
| 22 | B125 Interior (random) | 28.5 | 36.0 | -30.0 | 1000 |
| 23 | B125 Interior (biased) | 32.5 | 36.0 | -14.0 | 1000 |
| 24 | B125 Interior (biased) | 32.5 | 41.0 | -34.0 | 1000 |
| 25 | B125 Interior (biased) | 33.0 | 36.0 | -12.0 | 1000 |
| 26 | B125 Interior (biased) | 35.0 | 35.0 | 0.0 | 1000 |
| 27 | B125 Interior (biased) | 49.5 | 41.0 | 34.0 | 1000 |
| 28 | B125 Interior (biased) | 30.5 | 35.0 | -18.0 | 1000 |
| 29 | B125 Interior (biased) | 41.5 | 41.0 | 2.0 | 1000 |
| 30 | B125 Interior (biased) | 38.0 | 36.0 | 8.0 | 1000 |
| 31 | B125 Interior (biased) | 37.5 | 36.0 | 6.0 | 1000 |
| 32 | B125 Interior (biased) | 27.0 | 36.0 | -36.0 | 1000 |
| 33 | B125 Interior (biased) | 40.5 | 41.0 | -2.0 | 1000 |
| 34 | B125 Interior (biased) | 32.0 | 35.0 | -12.0 | 1000 |
| 35 | B125 Interior (biased) | 31.0 | 36.0 | -20.0 | 1000 |
| 36 | B125 Interior (biased) | 40.0 | 36.0 | 16.0 | 1000 |
| 37 | B125 Interior (biased) | 39.5 | 41.0 | -6.0 | 1000 |
| 38 | B125 Interior (biased) | 30.0 | 36.0 | -24.0 | 1000 |
| 39 | B125 Interior (biased) | 37.0 | 35.0 | 8.0 | 1000 |
| 40 | B125 Interior (biased) | 41.5 | 41.0 | 2.0 | 1000 |
| 41 | B125 Interior (biased) | 40.0 | 36.0 | 16.0 | 1000 |
| 42 | B125 Interior (biased) | 34.0 | 36.0 | -8.0 | 1000 |
| 43 | B125 Interior (biased) | 36.0 | 36.0 | 0.0 | 1000 |
| 44 | B125 Interior (biased) | 40.0 | 41.0 | -4.0 | 1000 |
| 45 | B125 Interior (biased) | 32.0 | 35.0 | -12.0 | 1000 |
| 46 | B125 Interior (biased) | 45.5 | 36.0 | 38.0 | 1000 |




| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|----|------------------------|---|--|---|---|
| 47 | B125 Interior (biased) | 32.0 | 35.0 | -12.0 | 1000 |
| 48 | B125 Interior (biased) | 34.5 | 36.0 | -6.0 | 1000 |
| 49 | B125 Interior (biased) | 31.0 | 36.0 | -20.0 | 1000 |
| 50 | B125 Interior (biased) | 41.0 | 41.0 | 0.0 | 1000 |
| 51 | B125 Interior (biased) | 34.5 | 36.0 | -6.0 | 1000 |
| 52 | B125 Interior (biased) | 34.0 | 41.0 | -28.0 | 1000 |
| 53 | B125 Interior (biased) | 34.0 | 41.0 | -28.0 | 1000 |
| 54 | B125 Interior (biased) | 29.5 | 35.0 | -22.0 | 1000 |
| 55 | B125 Interior (biased) | 30.5 | 36.0 | -22.0 | 1000 |
| 56 | B125 Interior (biased) | 41.0 | 35.0 | 24.0 | 1000 |
| 57 | B125 Interior (biased) | 40.5 | 36.0 | 18.0 | 1000 |
| 58 | B125 Interior (biased) | 32.5 | 35.0 | -10.0 | 1000 |
| 59 | B125 Interior (biased) | 31.5 | 36.0 | -18.0 | 1000 |
| 60 | B125 Interior (biased) | 36.5 | 36.0 | 2.0 | 1000 |
| 61 | B125 Interior (biased) | 31.0 | 35.0 | -16.0 | 1000 |
| 62 | B125 Interior (biased) | 30.5 | 35.0 | -18.0 | 1000 |
| 63 | B125 Interior (biased) | 38.5 | 36.0 | 10.0 | 1000 |
| 64 | B125 Interior (biased) | 28.0 | 36.0 | -32.0 | 1000 |
| 65 | B125 Interior (biased) | 42.5 | 41.0 | 6.0 | 1000 |
| 66 | B125 Interior (biased) | 40.5 | 35.0 | 22.0 | 1000 |
| 67 | B125 Interior (biased) | 40.5 | 36.0 | 18.0 | 1000 |
| 68 | B125 Interior (biased) | 29.5 | 36.0 | -26.0 | 1000 |
| 69 | B125 Interior (biased) | 38.0 | 41.0 | -12.0 | 1000 |

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: **A** Survey Unit: G10004 Classification: 3
 Building: 125
 Survey Unit Description: Interior Rooms 108C, 109, 110, 111
 Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 1 OF 12



0 FEET 30
 0 METERS 10

N →

Legend


- Scan Areas
- Bear & TSC Location
- Bear, TSC & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

52

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A Survey Unit: G10004 Classification: 3
 Building: 125
 Survey Unit Description: Interior Rooms 112, 113, 114, 114A, 115, 115A, 126, West Corridor, South Corridor
 Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 2 OF 12



53

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area:

Survey Unit: G10004

Classification: 3

Building: 125



Survey Unit Description: East Corridor, North Entry,

Total Floor Area: 1423 sq. m.

Total Area: 10104 sq. m.

Grid Size: N/A

SURVEY UNIT - MAP 3 OF 12



Scan Areas

SURVEY DEFINITIONS

- Smear & TSC Location
- Smear, TSC & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A

Survey Unit: G10004

Classification: 3

Building: 125


Survey Unit Description: Interior Rooms 108, 116, 117, 118, 119

Total Floor Area: 1423 sq. m.

Total Area: 10104 sq. m

Grid Size: N/A

SURVEY UNIT - MAP 4 OF 12



0 30
0 10
FEET
METERS




Legend

- Smear & TSC Location
- Smear, TSC & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit


RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A **Survey Unit: G10004** **Classification: 3**
Building: 125
Survey Unit Description: Interior Room 125 (middle and north end)
Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 5 OF 12




N →



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A Survey Unit: G10004 Classification: 3
 Building: 125
 Survey Unit Description: Interior Room 125 (south end)
 Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 6 OF 12



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A Survey Unit: G10004 Classification: 3
Building: 125
Survey Unit Description: Interior Rooms 101 to 103, North Corridor, 120, 121

Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

Classification: 3

Survey Unit Description: Interior Rooms 101 to 103, North Corridor, 120, 121

Grid Size: N/A

N

SURVEY MAP LEGEND

Smear & TSC Location

Smear, TSC & Sample Location

Open/Inaccessible Area




Area in Another Survey Unit

58

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A Survey Unit: G10004 Classification: 3
 Building: 125
 Survey Unit Description: Interior Rooms 122, 123, 124
 Total Floor Area: 1423 Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 8 OF 12



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: **A**
Building: 125

Survey Unit: G10004

Classification: 3



Survey Unit Description: Interior Ceiling (mid section)

Total Floor Area: 1423 sq. m.

Total Area: 10104 sq. m

Grid Size: N/A

SURVEY UNIT - MAP 9 OF 12




N →



RADIOLOGICAL CLOSEOUT SURVEY FOR

ea: **A** Survey Unit: **G10004** Classification: **3**
 125
 it Description: Interior Ceiling (north section)
 r Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: **N/A**

SURVEY UNIT - MAP 10 OF 12




61

RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: **A** Survey Unit: G10004 Classification: 3
 Building: 125
 Survey Unit Description: Interior Ceiling (south section)
 Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A



SURVEY UNIT - MAP 11 OF 12



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: **A** Survey Unit: G10004 Classification: 3
Building: 125
Survey Unit Description: Interior Upper Walls (north section)
Total Floor Area: 1423 sq. m. Total Area: 10104 sq. m Grid Size: N/A

SURVEY UNIT - MAP 12 OF 12



N →

Scan Areas

- SURVEY MAP LEGEND**
- Snare & TSC Location
 - ◇ Snare, TSC & Sample Location
 - Open/Inaccessible Area
 - Survey area in another location


TSA Alpha

G10005

| | | | | | | | |
|------------|------|------|------|------------------------|-----------|-----------|-------------|
| | | | | Instrument: | 1 1136 | 2 3114 | 3 394 QC |
| std. Dev.: | 19.0 | max: | 61.5 | Ave. Inst. background: | 3.8 | 3.8 | 5.0 cpm |
| mean: | 30.5 | min: | -4.9 | Instrument efficiency: | 21.1% | 22.0% | 21.8% |
| median: | 32.9 | | | Instrument MDA: | 48 | 48 | 48 dpm |

| | Surface Location | Total Alpha Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Alpha Activity (dpm/100cm ²) | Total Alpha DCGL (dpm/100cm ²) |
|-------|-------------------|---|--|---|---|
| 1 | Bldg 125 Exterior | 10.0 | 6.7 | 29.5 | 100 |
| 2 | Bldg 125 Exterior | 5.3 | 2.3 | 7.0 | 100 |
| 3 | Bldg 125 Exterior | 14.0 | 2.7 | 48.5 | 100 |
| 4 | Bldg 125 Exterior | 9.3 | 3.3 | 25.1 | 100 |
| 5 | Bldg 125 Exterior | 6.0 | 2.7 | 10.1 | 100 |
| 6 | Bldg 125 Exterior | 4.0 | 5.3 | 1.1 | 100 |
| 7 | Bldg 125 Exterior | 12.7 | 2.7 | 40.6 | 100 |
| 8 | Bldg 125 Exterior | 11.3 | 2.7 | 34.2 | 100 |
| 9 | Bldg 125 Exterior | 14.7 | 3.3 | 49.7 | 100 |
| 10 | Bldg 125 Exterior | 8.0 | 3.3 | 20.1 | 100 |
| 11 | Bldg 125 Exterior | 14.0 | 4.7 | 48.5 | 100 |
| 12 | Bldg 125 Exterior | 14.0 | 2.7 | 46.5 | 100 |
| 13 | Bldg 125 Exterior | 2.7 | 2.7 | -4.9 | 100 |
| 14 | Bldg 125 Exterior | 10.7 | 3.3 | 31.5 | 100 |
| 15 | Bldg 125 Exterior | 16.0 | 3.3 | 58.0 | 100 |
| 16 | Bldg 125 Exterior | 10.0 | 4.0 | 28.3 | 100 |
| 17 | Bldg 125 Exterior | 13.3 | 6.0 | 43.3 | 100 |
| 18 | Bldg 125 Exterior | 4.0 | 5.3 | 1.1 | 100 |
| 19 | Bldg 125 Exterior | 12.7 | 3.3 | 40.6 | 100 |
| 20 | Bldg 125 Exterior | 10.7 | 5.3 | 31.5 | 100 |
| 21 | Bldg 125 Exterior | 4.7 | 3.3 | 4.2 | 100 |
| 22 | Bldg 125 Exterior | 17.3 | 1.3 | 61.5 | 100 |
| 23 | Bldg 125 Exterior | 12.7 | 4.7 | 42.3 | 100 |
| 24 | Bldg 125 Exterior | 11.3 | 3.3 | 34.2 | 100 |
| 25 | Bldg 125 Exterior | 13.3 | 6.0 | 43.3 | 100 |
| 13 QC | Bldg 125 Exterior | 6.7 | 2.7 | 7.8 | 100 |
| 12 QC | Bldg 125 Exterior | 8.0 | 7.3 | 13.8 | 100 |

Unit Measurements



64

TSA Beta-Gamma


G10005

10/17/01

| | | | | | | | |
|------------|-------|------|--------|------------------------|-------------|-------------|---------------|
| | | | | Instrument: | <u>1136</u> | <u>3114</u> | <u>394</u> QC |
| std. Dev.: | 109.8 | max: | 127.5 | Ave. Inst. background: | 443.7 | 443.7 | 450.0 cpm |
| mean: | -36.7 | min: | -210.3 | Instrument efficiency: | 31.70% | 32.40% | 28.50% |
| median: | -8.5 | | | Instrument MDA: | 48 | 48 | 48 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Local Area Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Total β-γ DCGL (dpm/100cm ²) |
|-------|-------------------|---|--|---|--|
| 1 | Bldg 125 Exterior | 459 | 475 | 48.3 | 5000 |
| 2 | Bldg 125 Exterior | 387 | 415 | -174.9 | 5000 |
| 3 | Bldg 125 Exterior | 464 | 457 | 64.1 | 5000 |
| 4 | Bldg 125 Exterior | 408 | 420 | -110.1 | 5000 |
| 5 | Bldg 125 Exterior | 433 | 559 | -33.0 | 5000 |
| 6 | Bldg 125 Exterior | 435 | 437 | -27.4 | 5000 |
| 7 | Bldg 125 Exterior | 448 | 458 | 13.3 | 5000 |
| 8 | Bldg 125 Exterior | 421 | 395 | -70.0 | 5000 |
| 9 | Bldg 125 Exterior | 466 | 460 | 68.9 | 5000 |
| 10 | Bldg 125 Exterior | 377 | 386 | -210.3 | 5000 |
| 11 | Bldg 125 Exterior | 465 | 463 | 67.3 | 5000 |
| 12 | Bldg 125 Exterior | 456 | 431 | 38.0 | 5000 |
| 13 | Bldg 125 Exterior | 381 | 490 | -193.5 | 5000 |
| 14 | Bldg 125 Exterior | 460 | 419 | 50.4 | 5000 |
| 15 | Bldg 125 Exterior | 377 | 386 | -210.3 | 5000 |
| 16 | Bldg 125 Exterior | 441 | 385 | -8.3 | 5000 |
| 17 | Bldg 125 Exterior | 381 | 470 | -193.5 | 5000 |
| 18 | Bldg 125 Exterior | 413 | 444 | -94.7 | 5000 |
| 19 | Bldg 125 Exterior | 481 | 425 | 115.2 | 5000 |
| 20 | Bldg 125 Exterior | 480 | 469 | 112.1 | 5000 |
| 21 | Bldg 125 Exterior | 396 | 509 | -147.2 | 5000 |
| 22 | Bldg 125 Exterior | 485 | 416 | 127.5 | 5000 |
| 23 | Bldg 125 Exterior | 441 | 414 | -8.5 | 5000 |
| 24 | Bldg 125 Exterior | 441 | 507 | -8.3 | 5000 |
| 25 | Bldg 125 Exterior | 401 | 402 | -131.7 | 5000 |
| 13 QC | Bldg 125 Exterior | 385 | 463 | -228.1 | 5000 |
| 12 QC | Bldg 125 Exterior | 405 | 437 | -157.9 | 5000 |

Unit Measurements



Removable Activity - Alpha

G10005


10/17/01

standard deviation: 2.7 max: 11.8
mean: 1.2 min: -0.6
median: 0.0

| | | | |
|------------------------|-------|-------|---------|
| | 1 | 2 | 3 |
| Instrument: | 770 | 767 | 851 |
| Instrument background: | 0.1 | 0.2 | 0.0 cpm |
| Instrument efficiency: | 33.0% | 33.0% | 33.0% |
| Instrument MDA: | 6.2 | 7.1 | 4.0 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable α DCGL (dpm/100cm ²) |
|----|-------------------|---|-----------------------------------|---|--|
| 1 | Bldg 125 Exterior | 0.5 | 0.0 | 1.5 | 20 |
| 2 | Bldg 125 Exterior | 0.5 | 0.2 | 0.9 | 20 |
| 3 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 4 | Bldg 125 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 5 | Bldg 125 Exterior | 0.0 | 0.2 | -0.6 | 20 |
| 6 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 7 | Bldg 125 Exterior | 0.5 | 0.2 | 0.9 | 20 |
| 8 | Bldg 125 Exterior | 1.5 | 0.1 | 4.2 | 20 |
| 9 | Bldg 125 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 10 | Bldg 125 Exterior | 1.0 | 0.1 | 2.7 | 20 |
| 11 | Bldg 125 Exterior | 0.0 | 0.2 | -0.6 | 20 |
| 12 | Bldg 125 Exterior | 0.0 | 0.2 | -0.6 | 20 |
| 13 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 14 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 15 | Bldg 125 Exterior | 0.5 | 0.1 | 1.2 | 20 |
| 16 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 17 | Bldg 125 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 18 | Bldg 125 Exterior | 1.0 | 0.2 | 2.4 | 20 |
| 19 | Bldg 125 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 20 | Bldg 125 Exterior | 1.0 | 0.0 | 3.0 | 20 |
| 21 | Bldg 125 Exterior | 0.0 | 0.0 | 0.0 | 20 |
| 22 | Bldg 125 Exterior | 4.0 | 0.1 | 11.8 | 20 |
| 23 | Bldg 125 Exterior | 0.0 | 0.1 | -0.3 | 20 |
| 24 | Bldg 125 Exterior | 2.0 | 0.2 | 5.5 | 20 |
| 25 | Bldg 125 Exterior | 0.0 | 0.2 | -0.6 | 20 |

Unit Measurements



66


Removable Activity - Beta-Gamma

G10005

10/17/01

| | | | | | | | |
|---------------------|------|------|-------|------------------------|-------|-------|----------|
| | | | | Instrument: | 4 | 5 | 6 |
| | | | | | 835 | 911 | 700 |
| standard deviation: | 16.2 | max: | 44.0 | Instrument background: | 37.0 | 33.0 | 35.0 cpm |
| mean: | -1.0 | min: | -28.0 | Instrument efficiency: | 25.0% | 25.0% | 25.0% |
| median: | 0.0 | | | Instrument MDA: | 42.9 | 40.8 | 41.9 dpm |

| | Surface Location | Total Counts (cpm/100cm ²) | Bkgd (cpm/100cm ²) | Total Activity (dpm/100cm ²) | Removable β DCGL (dpm/100cm ²) |
|----|-------------------|---|-----------------------------------|---|--|
| 1 | Bldg 125 Exterior | 28.0 | 35.0 | -28.0 | 1000 |
| 2 | Bldg 125 Exterior | 30.5 | 33.0 | -10.0 | 1000 |
| 3 | Bldg 125 Exterior | 28.0 | 35.0 | -28.0 | 1000 |
| 4 | Bldg 125 Exterior | 34.0 | 35.0 | -4.0 | 1000 |
| 5 | Bldg 125 Exterior | 29.5 | 33.0 | -14.0 | 1000 |
| 6 | Bldg 125 Exterior | 34.5 | 35.0 | -2.0 | 1000 |
| 7 | Bldg 125 Exterior | 34.0 | 33.0 | 4.0 | 1000 |
| 8 | Bldg 125 Exterior | 41.0 | 37.0 | 16.0 | 1000 |
| 9 | Bldg 125 Exterior | 38.0 | 37.0 | 4.0 | 1000 |
| 10 | Bldg 125 Exterior | 37.0 | 37.0 | 0.0 | 1000 |
| 11 | Bldg 125 Exterior | 44.0 | 33.0 | 44.0 | 1000 |
| 12 | Bldg 125 Exterior | 33.0 | 33.0 | 0.0 | 1000 |
| 13 | Bldg 125 Exterior | 31.0 | 35.0 | -16.0 | 1000 |
| 14 | Bldg 125 Exterior | 38.0 | 35.0 | 12.0 | 1000 |
| 15 | Bldg 125 Exterior | 37.0 | 37.0 | 0.0 | 1000 |
| 16 | Bldg 125 Exterior | 35.0 | 35.0 | 0.0 | 1000 |
| 17 | Bldg 125 Exterior | 34.5 | 37.0 | -10.0 | 1000 |
| 18 | Bldg 125 Exterior | 28.5 | 33.0 | -18.0 | 1000 |
| 19 | Bldg 125 Exterior | 37.5 | 37.0 | 2.0 | 1000 |
| 20 | Bldg 125 Exterior | 29.5 | 35.0 | -22.0 | 1000 |
| 21 | Bldg 125 Exterior | 38.0 | 37.0 | 4.0 | 1000 |
| 22 | Bldg 125 Exterior | 42.0 | 37.0 | 20.0 | 1000 |
| 23 | Bldg 125 Exterior | 39.0 | 35.0 | 16.0 | 1000 |
| 24 | Bldg 125 Exterior | 36.5 | 33.0 | 14.0 | 1000 |
| 25 | Bldg 125 Exterior | 31.0 | 33.0 | -8.0 | 1000 |



RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: **A**

Survey Unit: G10005

Classification: 3

Building: 125





Survey Unit Description: Exterior

Total Roof Area: 1635 sq. m

Total Area: 2662 sq. m

Grid Size: N/A

SURVEY UNIT - MAP 1 OF 2





68


RADIOLOGICAL CLOSEOUT SURVEY FOR

Survey Area: A Survey Unit: G10005 Classification: 3
 Building: 125
 Survey Unit Description: Exterior
 Total Floor Area: 1635 sq. m Total Area: 2662 sq. m Grid Size: N/A

SURVEY UNIT - MAP 2 OF 2



Scan Areas



ATTACHMENT D

Chemical Data Summaries and Sample Maps

Asbestos Data Summary

| Sample Number | Material Sampled & Location | Analytical Results |
|----------------------|---|-------------------------|
| B125 | | |
| 125-10222001-315-101 | Room 103, non-friable gray, rubbery window caulking | None Detected |
| 125-10222001-315-102 | Room 103, non-friable gray & white, hard window caulking | 1% Point Count 0.5% |
| 125-10222001-315-103 | Room 104, friable gray & white, hard window caulking | 1% Point Count 0.25% |
| 125-10222001-315-104 | Room 104, friable gray & white, hard window caulking | 1% Point Count 0.25% |
| 125-10222001-315-105 | Room 108, friable gray & white, hard window caulking | 2% Point Count 0.75% |
| 125-10222001-315-106 | Room 125, friable, gross TSI debris on floor of Mech. Room | None Detected |
| 125-10222001-315-107 | Room 105A, friable gray & white, hard window caulking | 1% Point Count 0.25% |
| 125-10222001-315-108 | Room 108A, friable gray & white, hard window caulking | 2% Point Count 0.75% |
| 125-10222001-315-109 | Exterior, White caulking at base of exterior, corrugated metal wall, north side | 2% Point Count 0.5% |
| 125-10222001-315-110 | Exterior, White caulking at base of exterior, corrugated metal wall, north side | 1% Point Count 0.75% |
| 125-10222001-315-111 | Exterior, White caulking at base of exterior, corrugated metal wall, west side | 4% |
| 125-10222001-315-112 | Exterior, White caulking at base of exterior, corrugated metal wall, west side | 4% |
| 125-10222001-315-113 | Exterior, Black, rubbery caulking around exhaust louvers, east side | None Detected |
| 125-10222001-315-114 | Exterior, White caulking at base of exterior, corrugated metal wall, east side | 2% Point Count 1.25% |
| 125-10222001-315-115 | Exterior, White caulking at base of exterior, corrugated metal wall, east side | 2% Point Count 1.5% |

**ASBESTOS INSPECTION
AND
OPERATIONS AND MAINTENANCE PLAN
FOR
BUILDING 125
ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE
GOLDEN, COLORADO
SECTION I
(INTRODUCTION, METHODOLOGY, ASBESTOS INSPECTION)**

**PREPARED FOR
U.S. DEPARTMENT OF ENERGY
ROCKY FLATS FIELD OFFICE, BUILDING B131
P.O. BOX 928
GOLDEN, COLORADO 80402**

PROJECT NO. 108230

DECEMBER 31, 1996



11905 Borman Drive
St. Louis, MO 63146

(314) 569-1119

TABLE OF CONTENTS**Section I**

| | <u>PAGE</u> |
|---|--------------------|
| INTRODUCTION | 1 |
| METHODOLOGY | 2 |
| ASBESTOS INSPECTION | 2 |
| Space Inventory and Recommended Response Action Form | 2 |
| Bulk Sample Results and Photographic Log Form | 3 |
| Present and Future Exposure Potential Form | 3 |
| Inspection Findings | 3 |
| Space Inventory and Recommended Response Action Forms | |
| Bulk Sample Results and Photographic Log Forms | |
| Present and Future Exposure Potential Forms | |
| Drawings | |
| Photographs | |

Section II

| | <u>PAGE</u> |
|---|--------------------|
| OPERATIONS AND MAINTENANCE PLAN | 1 |
| Definitions | 1 |
| Training | 3 |
| Warning Labels | 5 |
| Personal Medical Monitoring | 6 |
| Response Actions | 7 |
| Preventive Measures | 8 |
| Operations and Maintenance Program | 8 |
| Surveillance and Reinspection | 17 |

TABLE OF CONTENTS (CONT.)**Section II (Cont.)**

| | <u>PAGE</u> |
|--|--------------------|
| Record Keeping and Updating of the O&M Plan | 19 |
| Transport and Disposal of Asbestos Waste | 20 |
| Record Keeping Forms | 20 |
| Respiratory Protection Program | 22 |
| OBSERVATIONS | 30 |

Section III

| | |
|--------------------|---|
| APPENDIX A. | OSHA ASBESTOS REGULATIONS FOR CONSTRUCTION INDUSTRY (29 CFR 1926.1101) |
| APPENDIX B. | OSHA ASBESTOS REGULATIONS FOR GENERAL INDUSTRY (29 CFR 1910.1001) |
| APPENDIX C. | OSHA RESPIRATORY PROTECTION (29 CFR 1910.134) |
| APPENDIX D. | EPA NESHAPS REVISION FOR ASBESTOS; FINAL RULE (40 CFR PART 61) |
| APPENDIX E. | EPA MODEL ACCREDITATION PLAN |
| APPENDIX F. | LABORATORY ANALYSIS AND LAB QUALIFICATIONS |
| APPENDIX G. | COLORADO AIR QUALITY CONTROL COMMISSION REGULATIONS |
| APPENDIX H. | RECORD KEEPING FORMS |
| APPENDIX I. | RESPIRATORY PROTECTION EVALUATION FORMS |

TABLE OF CONTENTS**Section I**

| | <u>PAGE</u> |
|---|--------------------|
| INTRODUCTION | 1 |
| METHODOLOGY | 2 |
| ASBESTOS INSPECTION | 2 |
| Space Inventory and Recommended Response Action Form | 2 |
| Bulk Sample Results and Photographic Log Form | 3 |
| Present and Future Exposure Potential Form | 3 |
| Inspection Findings | 3 |
| Space Inventory and Recommended Response Action Forms | |
| Bulk Sample Results and Photographic Log Forms | |
| Present and Future Exposure Potential Forms | |
| Drawings | |
| Photographs | |



INTRODUCTION

SITEX Environmental, Inc. (SITEX) was retained by the U.S. Department of Energy, Rocky Flats Field Office in Golden, Colorado to conduct an asbestos inspection and develop an operations and maintenance plan (O&M) for Building 125 located at the Rocky Flats Environmental Technology Site on U.S. Highway 93 in Golden, Colorado. This site is presently an industrial complex which was formerly used to manufacture nuclear weapons.

The asbestos inspection and O&M plan preparation was conducted in accordance with applicable asbestos regulations of the Occupational Safety and Health Administration (OSHA) and U.S. Environmental Protection Agency (EPA). Pertinent OSHA asbestos regulations are contained in Title 29 of the Code of Federal Regulations (CFR), Parts 1910.1001 and 1926.1101. EPA asbestos regulations adhered to were based on the Asbestos School Hazard Abatement Reauthorization Act (ASHARA) which amended the Asbestos Hazard Emergency Response Act (AHERA) or Title II of the Toxic Substance Control Act (TSCA) to extend training and accreditations described in the asbestos Model Accreditation Plan (MAP) to public and commercial buildings. AHERA was originally mandated to address asbestos-containing building materials located in public and private schools grades kindergarten through 12th. Regulations concerning ASHARA, AHERA and MAP are found in Title 40 of the CFR Part 763. OSHA and EPA regulations are presented in Appendices A through E.

The asbestos inspection included the collection of bulk material samples of suspect asbestos-containing materials in the form of surfacing materials, thermal system insulation and miscellaneous materials. The sampled materials are identified by space locations, area descriptions, sample numbers, photographic numbers and bulk material sample results. Asbestos-containing materials are further defined by material classification with a recommended response actions. Bulk sample results and a photographic log contain the percent and type of asbestos found in sampled materials and the photograph number of the photograph depicting the sampled material. Also presented are potential exposure concerns and a drawing indicating the spaces where asbestos-containing materials are located.

The O&M plan contains procedures to allow qualified asbestos personnel to properly address small-scale, short duration asbestos projects and record keeping forms to assist in documenting abatement projects conducted by qualified contractors. The projects would encompass asbestos removal, repair, encapsulation, enclosure or an emergency response or scheduled maintenance procedure.

This document, particularly the O&M plan, requires continual updating and record keeping by a qualified designated person of all activities related to asbestos-containing material and a current evaluation of their present and future exposure potentials. Material condition and potential for damage could change significantly with time. The owner is required to periodically reinspect the asbestos-containing materials or presumed asbestos-containing materials found in this building due to the potential changes in material condition. The qualified designated person should also ensure that all information is in accordance with current asbestos regulations. Regulations found in OSHA, EPA and the State of Colorado publications shall take precedence over this document at all times.

METHODOLOGY

Building 125 was inspected for suspect asbestos-containing materials which included surfacing materials, thermal system insulation and miscellaneous materials. Each material was identified by space number, quantified and then assessed for condition. Bulk material samples were collected of each suspect material utilizing AHERA and OSHA sampling protocols. Homogeneous determinations were made for asbestos-containing thermal system insulation which extended into more than one building space. All other materials (surfacing and miscellaneous) were described for each building space which eliminated the need to identify homogeneous spaces. The advantage of this strategy was to allow the users of this report immediate information regarding the asbestos-containing materials in any given space and not have to rely on a group of functional spaces which would define a homogeneous area.

Bulk material samples of suspect asbestos-containing materials were analyzed by polarized light microscopy (PLM) analysis with dispersion staining (DS) using EPA Method 600 IR-93/116 which is the present analytical method recommended by EPA. Analysis was performed by International Asbestos Testing Laboratory (IATL) located at 16000 Horizon Way, Unit 100 in Mount Laurel, New Jersey. IATL is accredited or approved by the National Institute of Science and Technology-National Voluntary Laboratory Accreditation Program (NIST-NVLAP), American Industrial Hygiene Association (AIHA) and Proficiency Analytical Testing (PAT) program. Laboratory analysis and qualifications for IATL are presented in Appendix F.

The O&M plan was developed using a combination of OSHA regulations and industry standards which are published in a variety of EPA documents. Recommended response actions were determined according to asbestos material condition; whether it was friable and its potential for present and future release of asbestos fibers. The adopted rating system was based on a subjective evaluation which included "low", "moderate" and "high" priority. Low would indicate a priority of concern less than moderate or high. Moderate would indicate a priority of concern higher than low and less than high and so on for high. Some ratings were also presented as a combination of low, moderate and high such as low to moderate or moderate to high.

ASBESTOS INSPECTION

The findings of the asbestos inspection and assessment determinations for Building 125 are documented on the Space Inventory and Recommended Response Action form, the Bulk Sample Results and Photographic Log form and the Present and Future Exposure Potential forms.

Space Inventory and Recommended Response Action Form

The Space Inventory and Recommended Response Action form includes the space number, asbestos material, material classification, approximate quantity, material condition and recommended response action. The **space number** indicates the area which was inspected for suspect asbestos-containing materials. **Asbestos materials** refer to the confirmed asbestos-containing materials which were in the inspected space. **Material classification** describes whether the asbestos material



ASBESTOS INSPECTION (CONT.)

Space Inventory and Recommended Response Action Form (Cont.)

was friable, Category I nonfriable or Category II nonfriable which are defined in Section II of this report. The **approximate quantity** indicates the amount of the particular asbestos material present in a space. **Present condition** indicates the present condition of the asbestos material and the type and amount of damage, if any. The **recommended response action** was based on material classification and present condition. The recommended response action was chosen to minimize fiber exposure to building occupants and the environment.

Bulk Sample Results and Photographic Log Form

The Bulk Sample Results and Photographic Log form is composed of the space number, description of area, sample number, material sampled, photograph number and results. The **space number** is the same as previously mentioned. The **description of area** provides recognizable names which indicate the activity or function of the space. The **sample number** consists of the building number followed by standard counting numbers to indicate a unique sample number. **Material sampled** refers to the actual sampled material in a particular space. The **photograph number** indicates the photographs taken of bulk material samples and details of building spaces. **Results** are the determined laboratory analysis of the collected bulk material samples.

Present and Future Exposure Potential Form

The Present and Future Exposure Potential form consists of headings stating space number, asbestos material, friable, present condition, damage potential and exposure potential. Exposure potential is subdivided into headings of present (no response action); future (response action completed); and future (response action not completed). The **space number**, **asbestos material** and **present condition** were previously defined. **Friable** warrants a yes or no response based on whether the material is friable or nonfriable. **Damage potential** is indicated as low, moderate or high which is based on damage from physical contact, material location and deterioration factors such as air movement, vibration and water damage. The **exposure potential** also indicated as low, moderate or high is based on the asbestos material, whether it is friable, the present condition and the damage potential. Exposure potential is further defined as **present** with no response action being performed and **future** with and without the recommended response action being completed.

Inspection Findings

The completed Space Inventory and Recommended Response Action form, Bulk Sample Results and Photographic Log form and Present and Future Exposure Potential form for Building 125 are as follows. Also presented is a building drawing which indicates space numbers, asbestos materials present and photograph numbers. The photographs which are referred to in the Space Inventory and Recommended Response Action form, the Bulk Sample Results and Photographic Log form and the drawing are presented following the building drawing.

BUILDING 125

Space Inventory and Recommended Response Action

SPACE INVENTORY AND RECOMMENDED RESPONSE ACTION

Building No: 125
Location: Rocky Flats

Page No: 1
Date: October 10, 1996

| Space No. | Asbestos Material | Material Classification | Approximate Quantity | Material Condition | Recommended Response Action |
|-----------|---|-------------------------|----------------------|--------------------|-----------------------------------|
| 100 | 9" x 9" floor tile, beige | nonfriable, I | 380 square feet | no damage | operations and maintenance |
| 100 | 9" x 9" floor tile, tan | nonfriable, I | 190 square feet | no damage | operations and maintenance |
| 100 | 12" x 12" floor tile, white, beneath water fountain | nonfriable, I | 10 square feet | no damage | operations and maintenance |
| 100 | flooring and mastic beneath carpet | nonfriable, I | 60 square feet | no damage | operations and maintenance |
| 100 | pipng, near yellow ladder | friable | 80 square feet | no damage | operations and maintenance |
| 100 | cementitious wall | nonfriable, II | 700 square feet | no damage | operations and maintenance |
| 100 | expansion joint | nonfriable, II | 20 square feet | no damage | operations and maintenance |
| 100 | pipe elbows/fittings, outside Space 108D | friable | 4 | 4/damaged | repair/operations and maintenance |
| 100 | pipe elbows/fittings (above ceiling) | friable | 100 | 8/damaged | reapir/operations and maintenance |
| 101 | 9" x 9" floor tile, beige | nonfriable, I | 40 square feet | no damage | operations and maintenance |
| 102 | flooring beneath carpet | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 103 | 9" x 9" floor tile, beige | nonfriable, I | 425 square feet | no damage | operations and maintenance |

SPACE INVENTORY AND RECOMMENDED RESPONSE ACTION

Building No: 125 (Cont.)

Location: Rocky Flats

Page No: 2

Date: October 10, 1996

| Space No. | Asbestos Material | Material Classification | Approximate Quantity | Material Condition | Recommended Response Action |
|-----------|-------------------------------------|-------------------------|----------------------|--------------------|-----------------------------|
| 104 | 9" x 9" floor tile, green | nonfriable, I | 350 square feet | no damage | operations and maintenance |
| 104 | 9" x 9" floor tile, beige | nonfriable, I | 80 square feet | no damage | operations and maintenance |
| 104 | pipe elbows | friable | 4 | no damage | operations and maintenance |
| 104A | 9" x 9" floor tile, beige | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 105 | 9" x 9" floor tile, green | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 105A | 9" x 9" floor tile, beige | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 106 | 9" x 9" floor tile, beige | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 107 | 9" x 9" floor tile, green | nonfriable, I | 425 square feet | no damage | operations and maintenance |
| 108 | 9" x 9" floor tile, green | nonfriable, I | 100 square feet | no damage | operations and maintenance |
| 108A | flooring beneath carpet | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 108B | flooring beneath carpet | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 108C | pipe elbows, above ceiling | friable | 8 | no damage | operations and maintenance |
| 108C | fume hood cementitious panels | nonfriable, II | 25 square feet | no damage | operations and maintenance |
| 112 | pipe elbows/fittings, above ceiling | friable | 10 | no damage | operations and maintenance |

P2

SPACE INVENTORY AND RECOMMENDED RESPONSE ACTION

Building No: 125 (Cont.)

Location: Rocky Flats

Page No: 3

Date: October 10, 1996

| Space No. | Asbestos Material | Material Classification | Approximate Quantity | Material Condition | Recommended Response Action |
|-----------|--|-------------------------|----------------------|------------------------|-----------------------------------|
| 115 | sheeting flooring, beige | nonfriable, I | 550 square feet | no damage | operations and maintenance |
| 116 | sheet flooring, beige | nonfriable, I | 600 square feet | no damage | operations and maintenance |
| 117 | 9" x 9" floor tile, beige | nonfriable, I | 550 square feet | no damage | operations and maintenance |
| 118 | 9" x 9" floor tile, beige | nonfriable, I | 550 square feet | no damage | operations and maintenance |
| 119 | 9" x 9" floor tile, beige | nonfriable, I | 550 square feet | no damage | operations and maintenance |
| 120 | flooring beneath carpet | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 120 | blocks attached to gas expansion equipment | nonfriable, II | 12 square feet | no damage | operations and maintenance |
| 121 | flooring beneath carpet | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 122A | pipe elbow/fittings | friable | 25 | 5/damaged | repair/operations and maintenance |
| 123 | 9" x 9" floor tile, beige | nonfriable, I | 225 square feet | no damage | operations and maintenance |
| 125 | pipng | friable | 225 linear feet | <3 linear feet/damaged | repair/operations and maintenance |
| 125 | pipe elbow/fittings | friable | 100 | <10/damaged | repair/operations and maintenance |

SPACE INVENTORY AND RECOMMENDED RESPONSE ACTION

Building No: 125 (Cont.)

Location: Rocky Flats


Page No: 4

Date: October 10, 1996

| Space No. | Asbestos Material | Material Classification | Approximate Quantity | Material Condition | Recommended Response Action |
|-----------|----------------------|-------------------------|----------------------|--------------------|-----------------------------|
| 125 | expansion tank (2) | friable | 6 square feet | no damage | operations and maintenance |
| 126 | 2' x 4' ceiling tile | friable | 70 square feet | no damage | operations and maintenance |

Sylvester B. Douglas

Management Planner/Inspector's Name


Signature


Management Planner/Inspector ID

84

BUILDING 125

Bulk Sample Results and Photographic Log

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125
Location: Rocky Flats

Page No. 1
Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|--|-----------|--|
| 00 | Common Area | 125-073 | 12" x 12" floor tile, white | 52 | None Detected |
| 100 | Hall | 125-054 | 9" x 9" floor tile, light green | 35 | <1% Chrysotile (tile) None Detected (mastic) |
| 100 | Hall | 125-055 | 9" x 9" floor tile, beige | 36 | 10% Chrysotile (tile) 5% Chrysotile (mastic) |
| 100 | Hall | 125-056 | 12" x 12" floor tile, white | 35 | None Detected |
| 100 | Hall | 125-057 | 9" x 9" floor tile, tan | 35 | 4% Chrysotile (tile) None Detected (mastic) |
| 100 | Hall | 125-058 | flooring beneath carpet, outside Space 126 | 39 | 5% Chrysotile (tile) 6% Chrysotile (mastic) |
| 100 | Hall | 125-059 | pipe, condensate steam purge above ceiling | 40 | 35% Amosite |
| 100 | Hall | 125-060 | pipe, steam 125 above ceiling | 40 | 15% Chrysotile |
| 100 | Hall | 125-074 | 12" x 12" floor tile, white beneath water fountain | 53 | 10% Chrysotile (tile) 10% Chrysotile (mastic) |
| 100 | Hall | 125-076 | cementitious wall | 55 | 35% Chrysotile |
| 100 | Hall | 125-081 | expansion joint, building addition | 59 | 70% Chrysotile |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Location: Rocky Flats

Page No. 2

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|---|-----------|---|
| 100 | Hall | 125-082 | pipe elbow, domestic water above ceiling | 60 | 5.3% Chrysotile 4.5% Amosite |
| 101 | Office | 125-062 | flooring beneath carpet, east door | 42 | None Detected (tile) None Detected (mastic) |
| 101 | Office | 125-063 | 9" x 9" floor tile, beige | 43 | 15% Chrysotile |
| 101E | Office | 125-061 | straw wall | 41 | None Detected |
| 108 | Office | 125-071 | 9" x 9" floor tile, green | 50 | 1.8% Chrysotile (tile) None Detected (mastic) |
| 108 | Office | 125-072 | cementitious wall | 51 | 30% Chrysotile |
| 108C | Laboratory | 125-069 | cementitious panels in fumehood | 48 | 30% Chrysotile |
| 108C | Laboratory | 125-070 | counter material | 49 | None Detected |
| 109 | Equipment Area | 125-068 | 2' x 4' ceiling tile | 47 | None Detected |
| 114 | Office | 125-067 | 12" x 12" floor tile, white | 46 | None Detected (tile) None Detected (mastic) |
| 115 | Laboratory | 125-079 | sheet flooring, beige | 57 | 25% Chrysotile (flooring) None Detected (mastic) |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Location: Rocky Flats

Page No. 3

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|---|-----------|---------------------------|
| 116 | Laboratory | 125-080 | lab table material | 58 | None Detected |
| 119 | Laboratory | 125-075 | sink counter | 54 | None Detected |
| 119 | Laboratory | 125-077 | pipe elbow/fitting domestic cold water | 56 | None Detected |
| 119 | Laboratory | 125-078 | pipe elbow/fitting domestic hot water | 56 | None Detected |
| 120 | Laboratory | 125-064 | blocks attached to gas expansion equipment | 44 | 70% Chrysotile |
| 122A | Pipechase | 125-065 | pipe elbow, domestic cold water | 45 | 3% Chrysotile, 2% Amosite |
| 122A | Pipechase | 125-066 | pipe elbow, domestic hot water | 45 | 4% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-001 | pipe elbow, domestic cold water | 1 | 20% Amosite |
| 125 | Mechanical Room | 125-002 | pipe elbow, domestic hot water | 2 | Not Analyzed |
| 125 | Mechanical Room | 125-003 | pipe elbow, domestic hot water return | 3 | Not Analyzed |
| 125 | Mechanical Room | 125-004 | drywall | 4 | None Detected |

AP

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Location: Rocky Flats

Page No. 4

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|--|-----------|-----------------------------|
| 125 | Mechanical Room | 125-005 | pipe elbow, heating water supply | 5 | 5% Amosite |
| 125 | Mechanical Room | 125-006 | pipe, unlabeled beneath Sample 125-006 | 6 | None Detected |
| 125 | Mechanical Room | 125-007 | pipe elbow, domestic cold water | 7 | 2% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-008 | expansion tank insulation | 8 | 15% Chrysotile, 15% Amosite |
| 125 | Mechanical Room | 125-009 | expansion tank insulation | 8 | Not Analyzed |
| 125 | Mechanical Room | 125-010 | expansion tank insulation | 8 | Not Analyzed |
| 125 | Mechanical Room | 125-011 | pipe, steam 15 | 9 | 65% Amosite |
| 125 | Mechanical Room | 125-012 | pipefitting, steam 15 | 9 | 20% Amosite |
| 125 | Mechanical Room | 125-013 | pipe elbow, domestic cold water | 13 | 3% Chrysotile, 2% Amosite |
| 125 | Mechanical Room | 125-014 | pipefitting, cooling water supply | 14 | 20 % Chrysotile |
| 125 | Mechanical Room | 125-015 | pipefitting, cooling water return | 14 | Not Analyzed |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Location: Rocky Flats

Page No. 5

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|--|-----------|---------------------------|
| 125 | Mechanical Room | 125-016 | pipe, steam 15 | 12 | 30% Amosite |
| 125 | Mechanical Room | 125-017 | pipe elbow, steam 15 | 12 | 8% Chrysotile, 2% Amosite |
| 125 | Mechanical Room | 125-018 | pipe elbow, heating water return | 12 | 2% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-019 | pipe elbow, heating water supply | 16 | Not Analyzed |
| 125 | Mechanical Room | 125-020 | pipe, heating water supply, labeled asbestos | 11 | None Detected |
| 125 | Mechanical Room | 125-021 | pipe, condensate steam | 10 | 15% Amosite |
| 125 | Mechanical Room | 125-022 | pipe elbow, condensate steam | 10 | 3% Chrysotile, 2% Amosite |
| 125 | Mechanical Room | 125-023 | fiber glass ductwrap | 21 | None Detected |
| 125 | Mechanical Room | 125-024 | gray vibration isolator | 22 | None Detected |
| 125 | Mechanical Room | 125-025 | fiber glass ductwrap | 15 | None Detected |
| 125 | Mechanical Room | 125-026 | cloth vibration isolator return | 15 | None Detected |
| 125 | Mechanical Room | 125-027 | pipe elbow, freon line | 17 | 3% Chrysotile, 2% Amosite |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Page No. 6

Location: Rocky Flats

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|-----------------------------------|-----------|-----------------------------|
| 125 | Mechanical Room | 125-028 | pipefitting, cooling water supply | 19 | 1% Amosite |
| 125 | Mechanical Room | 125-029 | pipefitting, cooling water return | 19 | Not Analyzed |
| 125 | Mechanical Room | 125-030 | fiber glass ductwrap | 26 | None Detected |
| 125 | Mechanical Room | 125-031 | black vibration isolator | 27 | None Detected |
| 125 | Mechanical Room | 125-032 | expansion tank insulation | 28 | 10% Chrysotile |
| 125 | Mechanical Room | 125-033 | expansion tank insulation | 28 | Not Analyzed |
| 125 | Mechanical Room | 125-034 | expansion tank insulation | 28 | Not Analyzed |
| 125 | Mechanical Room | 125-035 | pipe insulation, steam 125 | 29 | 10% Chrysotile, 15% Amosite |
| 125 | Mechanical Room | 125-036 | pipe elbow, steam 125 | 29 | 3% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-037 | pipe, steam 15 | 32 | Not Analyzed |
| 125 | Mechanical Room | 125-038 | pipe elbow, steam 15 | 32 | Not Analyzed |
| 125 | Mechanical Room | 125-039 | black vibration isolator | 31 | None Detected |
| 125 | Mechanical Room | 125-040 | pipe elbow, domestic cold water | 24 | None Detected |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125 (Cont.)

Location: Rocky Flats

Page No. 7

Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|-----------------------------------|-----------|---|
| 125 | Mechanical Room | 125-041 | pipe elbow, domestic hot water | 23 | 3% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-042 | pipefitting, domestic cold water | 30 | Not Analyzed |
| 125 | Mechanical Room | 125-043 | pipe, condensate steam | 18 | 20% Amosite |
| 125 | Mechanical Room | 125-044 | pipe elbow, condensate steam | 18 | 2% Chrysotile, 3% Amosite |
| 125 | Mechanical Room | 125-045 | duct seam tape | 25 | None Detected |
| 125 | Mechanical Room | 125-046 | pipefitting, cooling water return | 20 | 3% Chrysotile, 5% Amosite |
| 125 | Mechanical Room | 125-047 | pipefitting, cooling water supply | 20 | Not Analyzed |
| 126 | Closet | 125-048 | 12" x 12" floor tile, white | 33 | <1% Chrysotile (tile) None Detected (mastic) |
| 126 | Closet | 125-049 | base molding, brown | 33 | None Detected |
| 126 | Closet | 125-050 | 2' x 4' ceiling tile | 34 | <1% Chrysotile, 3% Amosite |
| 126 | Closet | 125-051 | drywall | 37 | None Detected |

BULK SAMPLE RESULTS AND PHOTOGRAPHIC LOG

Building No: 125
Location: Rocky Flats

Page No. 8
Date: October 10, 1996

| Space No. | Description of Area | Sample No. | Material Samples | Photo No. | Results |
|-----------|---------------------|------------|---------------------------------------|-----------|---------------------------|
| 126 | Closet | 125-052 | pipe elbow, hot water supply | 38 | 5% Chrysotile, 2% Amosite |
| 126 | Closet | 125-053 | pipefitting, hot water return | 38 | Not Analyzed |
| | Above Ceiling | | east area, looking south | 61 | |
| | Above Ceiling | | above laboratories, looking southwest | 62 | |
| | Above Ceiling | | north area, looking west | 63 | |
| Exterior | Roof, East Side | 25 | roof | | None Detected |

Asbestos inspection, assessment and sampling have been conducted by an EPA and state of Colorado accredited inspector in accordance with 40 CFR 763, who has completed an approved course under the Asbestos Hazard Emergency Response Act (AHERA).

Inspector's Certification No. [REDACTED]

Name Sylvester B. Douglas

Signature of Inspector *Sylvester B. Douglas*

BUILDING 125

Present and Future Exposure Potential

PRESENT AND FUTURE EXPOSURE POTENTIAL

Building No: 125
Location: Rocky Flats

Page: 1
Date: October 10, 1996

Sylvester B. Douglas
Management Planner/Inspector's Name

Sylvester Douglas
Signature

[REDACTED]
Management Planner/Inspector ID

| | | | | | EXPOSURE POTENTIAL | | |
|-----------|---|---------|-------------------|------------------|--------------------|---------------------------|-------------------------------|
| | | | | | Present | Future | |
| Space No. | Asbestos Material | Friable | Present Condition | Damage Potential | No Response Action | Response Action Completed | Response Action Not Completed |
| 100 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 100 | 9" x 9" floor tile, tan | no | no damage | low | low | low | low |
| 100 | 12" x 12" floor tile, white, beneath water fountain | no | no damage | low | low | low | low |
| 100 | flooring and mastic beneath carpet | no | no damage | low | low | low | low |
| 100 | pipng, near yellow ladder | yes | no damage | low | low | low | low to moderate |
| 100 | cementitious wall | no | no damage | low | low | low | low |
| 100 | expansion joint | no | no damage | low | low | low | low |

PRESENT AND FUTURE EXPOSURE POTENTIAL (CONT.)

Building No: 125
Location: Rocky Flats

Page: 2
Date: October 10, 1996

Sylvester B. Douglas
Management Planner/Inspector's Name

Sylvester Douglas
Signature

[REDACTED]
Management Planner/Inspector ID

| | | | | | EXPOSURE POTENTIAL | | |
|-----------|--|---------|-------------------|------------------|--------------------|---------------------------|-------------------------------|
| | | | | | Present | Future | |
| Space No. | Asbestos Material | Friable | Present Condition | Damage Potential | No Response Action | Response Action Completed | Response Action Not Completed |
| 100 | pipe elbows/fittings, outside Space 108D | yes | no damage | low to moderate | low to moderate | low | low to moderate |
| 100 | pipe elbows/fittings (above ceiling) | yes | 8 damaged | low | low to moderate | low | low to moderate |
| 101 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 102 | flooring beneath carpet | no | no damage | low | low | low | low |
| 103 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 104 | 9" x 9" floor tile, green | no | no damage | low | low | low | low |
| 104 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 104 | pipe elbows | yes | no damage | low | low | low | low |
| 104A | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |

PRESENT AND FUTURE EXPOSURE POTENTIAL (CONT.)

Building No: 125
Location: Rocky Flats

Page: 3
Date: October 10, 1996

Sylvester B. Douglas
Management Planner/Inspector's Name

SD
Signature

[REDACTED]
Management Planner/Inspector ID

| | | | | | EXPOSURE POTENTIAL | | |
|-----------|-------------------------------|---------|-------------------|------------------|---------------------|---------------------------|-------------------------------|
| | | | | | Present | Future | |
| Space No. | Asbestos Material | Friable | Present Condition | Damage Potential | No. Response Action | Response Action Completed | Response Action Not Completed |
| 105 | 9" x 9" floor tile, green | no | no damage | low | low | low | low |
| 105A | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 106 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 107 | 9" x 9" floor tile, green | no | no damage | low | low | low | low |
| 108 | 9" x 9" floor tile, green | no | no damage | low | low | low | low |
| 108A | flooring beneath carpet | no | no damage | low | low | low | low |
| 108B | flooring beneath carpet | no | no damage | low | low | low | low |
| 108C | pipe elbows, above ceiling | yes | no damage | low | low | low | low |
| 108C | fume hood cementitious panels | no | no damage | low | low | low | low |

PRESENT AND FUTURE EXPOSURE POTENTIAL (CONT.)

Building No: 125
Location: Rocky Flats

Page: 4
Date: October 10, 1996

Sylvester B. Douglas
Management Planner/Inspector's Name

SD
Signature

[REDACTED]
Management Planner/Inspector ID

| | | | | | EXPOSURE POTENTIAL | | |
|-----------|--|---------|-------------------|------------------|--------------------|---------------------------|-------------------------------|
| | | | | | Present | Future | |
| Space No. | Asbestos Material | Friable | Present Condition | Damage Potential | No Response Action | Response Action Completed | Response Action Not Completed |
| 112 | pipe elbows/fittings, above ceiling | yes | no damage | low | low | low | low |
| 115 | sheeting flooring, beige | no | no damage | low | low | low | low to moderate |
| 116 | sheet flooring, beige | no | no damage | low | low | low | low |
| 117 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 118 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 119 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 120 | flooring beneath carpet | no | no damage | low | low | low | low |
| 120 | blocks attached to gas expansion equipment | no | no damage | low to mod. | low to mod. | low | low to moderate |
| 121 | flooring beneath carpet | no | no damage | low | low | low | low |

98

PRESENT AND FUTURE EXPOSURE POTENTIAL (CONT.)

Building No: 125
Location: Rocky Flats

Page: 5
Date: October 10, 1996

Sylvester B. Douglas
Management Planner/Inspector's Name

SD
Signature

[REDACTED]
Management Planner/Inspector ID

| | | | | | EXPOSURE POTENTIAL | | |
|-----------|---------------------------|---------|-------------------------|------------------|--------------------|---------------------------|-------------------------------|
| | | | | | Present | Future | |
| Space No. | Asbestos Material | Friable | Present Condition | Damage Potential | No Response Action | Response Action Completed | Response Action Not Completed |
| 122A | pipe elbow/fittings | yes | 5 damaged | low to mod. | low | low | low to moderate |
| 123 | 9" x 9" floor tile, beige | no | no damage | low | low | low | low |
| 125 | pipng | | <3 linear feet damaged | low | low to mod. | low | low to moderate |
| 125 | pipe elbow/fittings | yes | <10 linear feet damaged | low | low to mod. | low | low to moderate |
| 125 | expansion tank (2) | yes | no damage | low | low | low | low to moderate |
| 126 | 2' x 4' ceiling tile | yes | no damage | low | low | low | low to moderate |

BUILDING 125

Drawing

BUILDING 125

ASBESTOS NOTES


| Space | Asbestos Material | Photo No. |
|-------|--|---|
| 100 | floor tile; pipe; walls expansion joint | 35, 36, 39, 40, 53, 55, 59, 60 43 |
| 101 | floor tile | |
| 102 | flooring | |
| 103 | floor tile | |
| 104 | floor tile; pipe | |
| 104A | floor tile | |
| 105 | floor tile | |
| 105A | floor tile | |
| 106 | floor tile | |
| 107 | floor tile | |
| 108 | floor tile | 50, 51 |
| 108A | flooring | |
| 108B | flooring | |
| 108C | pipe (above ceiling); fume hood | 48 |
| 112 | pipe | |
| 115 | sheet flooring | 57 |
| 116 | sheet flooring | |
| 117 | floor tile | |
| 118 | floor tile | |
| 119 | floor tile | |
| 120 | flooring, equipment block | 44 |
| 121 | flooring | |
| 122A | pipe | 45 |
| 123 | floor tile | |
| 125 | pipe; expansion tank | 1-32 |
| 126 | ceiling tile | 34 |

Note: Asbestos-containing building materials were not found in Spaces:

00, 109, 110, 111, 113, 114, 124

LEGEND

Space No. ○
Wall —



FLOOR PLAN

101
DATE 10-31-98
SHEET NO. 4

ASBESTOS INSPECTION

SITEX
Environmental Inc.

11803 Berman Drive
St. Louis, MO 63146

U.S. DEPARTMENT OF ENERGY
ROCKY FLATS FIELD OFFICE
GOLDEN, COLORADO 80402

NO. DATE REVISIONS


BUILDING 125

BUILDING 125

Photographs




1



2




3




4




5




6




7




8



9




10




11



12




13



14




15




16




17




18



19




20




21



22



23




24




25




26




27




28




29




30



31



32




33



34




35




36




37




38




39




40




41




42



43




44



45



46



47

[Handwritten signature]




48



49



50




51




52




53




54




55



56




57



58




59




60




61



62



63



64

APPENDIX F

**LABORATORY ANALYSIS AND
LAB QUALIFICATIONS**

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521686**Client No.:** 125-001**Material Description:** White Insulation**Location:**% Asbestos

20

Type

Amosite

% Non-Asbestos Fibrous Material

20

Type

Mineral Wool

% Non-Fibrous Material

60

Lab No. 521687**Client No.:** 125-002**Material Description:** Sample Not Analyzed**Location:**% Asbestos

Not Analyzed

Type% Non-Asbestos Fibrous Material

Not Analyzed

Type% Non-Fibrous Material**Lab No.** 521688**Client No.:** 125-003**Material Description:** Sample Not Analyzed**Location:**% Asbestos

Not Analyzed

Type% Non-Asbestos Fibrous Material

Not Analyzed

Type% Non-Fibrous Material**Lab No.** 521689**Client No.:** 125-004**Material Description:** White/Tan**Location:**

Sheetrock

(No JtCompound)

% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

15

Type

Cellulose

% Non-Fibrous Material

85

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Date:** SEP 07 1996**Approved By:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521690**Client No.:** 125-005**Material Description:** White Insulation**Location:**% Asbestos

5

Type

Amosite

% Non-Asbestos Fibrous Material

30

Type

Mineral Wool

% Non-Fibrous Material35
ah**Lab No.** 521691**Client No.:** 125-006**Material Description:** White/Yellow/Tan**Location:** Lag/Insulation% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

60

Type

Fibrous Glass

% Non-Fibrous Material

20

15

Mineral Wool

5

Cellulose

Lab No. 521692**Client No.:** 125-007**Material Description:** White/Tan**Location:** Insulation/Lag% Asbestos

3

Type

Amosite

% Non-Asbestos Fibrous Material

25

Type

Mineral Wool

% Non-Fibrous Material

65

2

Chrysotile

5

Cellulose

Lab No. 521693**Client No.:** 125-008**Material Description:** White/Tan**Location:** Insulation/Lag% Asbestos

15

Type

Chrysotile

% Non-Asbestos Fibrous Material

10

Type

Cellulose

% Non-Fibrous Material

60

15

Amosite

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Approved:** Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 07 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521694**Client No.:** 125-009**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521695**Client No.:** 125-010**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521696**Client No.:** 125-011**Material Description:** Gray Insulation**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

65

Amosite

None Detected

None Detected

35

Lab No. 521697**Client No.:** 125-012**Material Description:** White Lag/Insulation**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

20

Amosite

50

Fibrous Glass

25

5

Cellulose

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Approved By:**Frank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 07 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521698**Client No.:** 125-013**Material Description:** White Insulation/Lag**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

2

Amosite

20

Mineral Wool

70

3

Chrysotile

5

Cellulose

Lab No. 521699**Client No.:** 125-014**Material Description:** White Insulation/Lag**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

20

Chrysotile

10

Mineral Wool

60

10

Cellulose

Lab No. 521700**Client No.:** 125-015**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521701**Client No.:** 125-016**Material Description:** White Insulation/Lag**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

30

Amosite

10

Cellulose

60

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Approved By:**Frank E. Ehrenfeld, III
Laboratory Director**Date:****SEP 07 1996**

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521702
Client No.: 125-017**Material Description:** White Insulation
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 8 | Chrysotile | 25 | Mineral Wool | 65 |
| 2 | Amosite | | | |

Lab No. 521703
Client No.: 125-018**Material Description:** White
Location: Insulation/Lag

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 3 | Amosite | 20 | Mineral Wool | 65 |
| 2 | Chrysotile | 10 | Cellulose | |

Lab No. 521704
Client No.: 125-019**Material Description:** Sample Not Analyzed
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| Not Analyzed | | Not Analyzed | | |

Lab No. 521705
Client No.: 125-020**Material Description:** White/Yellow/Brown
Location: Lag/Insulation

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | 50 | Fibrous Glass | 15 |
| | | 30 | Mineral Wool | |
| | | 5 | Cellulose | |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Approved By:** Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 07 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521706**Client No.:** 125-021**Material Description:** Gray/White**Location:** Insulation/Lag% Asbestos

15

Type

Amosite

% Non-Asbestos Fibrous Material

20

Type

Cellulose

% Non-Fibrous Material

65

Lab No. 521707**Client No.:** 125-022**Material Description:** White Insulation/Lag**Location:**% Asbestos

3

Type

Chrysotile

% Non-Asbestos Fibrous Material

10

Type

Mineral Wool

% Non-Fibrous Material

65

2

Amosite

20

Cellulose

Lab No. 521708**Client No.:** 125-023**Material Description:** Tan Lag**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

90

Type

Cellulose

% Non-Fibrous Material

10

Lab No. 521709**Client No.:** 125-024**Material Description:** Black/Silver**Location:** Insulation% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

40

Type

Fibrous Glass

% Non-Fibrous Material

60

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Approved**Frank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 07 1998

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521710**Client No.:** 125-025**Material Description:** White Lag**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

80

Type

Cellulose

% Non-Fibrous Material

20

Lab No. 521711**Client No.:** 125-026**Material Description:** Black/White**Location:**

Insulation

% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

50

Type

Fibrous Glass

% Non-Fibrous Material

50

Lab No. 521712**Client No.:** 125-027**Material Description:** White/Tan**Location:**

Insulation

% Asbestos

3

Type

Chrysotile

% Non-Asbestos Fibrous Material

20

Type

Mineral Wool

% Non-Fibrous Material

70

2

Amosite

5

Cellulose

Lab No. 521713**Client No.:** 125-028**Material Description:** White Lag/Insulation**Location:**% Asbestos

4

Type

Chrysotile

% Non-Asbestos Fibrous Material

10

Type

Mineral Wool

% Non-Fibrous Material

25

1

Amosite

60

Cellulose

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Approved**Frank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 07 1996

SEP 07 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521714
Client No.: 125-029**Material Description:** Sample Not Analyzed
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| Not Analyzed | | Not Analyzed | | |

Lab No. 521715
Client No.: 125-030**Material Description:** Tan/White Lag/Paint
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|--------------|-------------------------------|
| None Detected | None Detected | 88 | Cellulose | 10 |
| | | 2 | Mineral Wool | |

Lab No. 521716
Client No.: 125-031**Material Description:** White/Black
Location: Insulation

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | 80 | Fibrous Glass | 20 |

Lab No. 521717
Client No.: 125-032**Material Description:** White Insulation
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 10 | Chrysotile | 25 | Mineral Wool | 65 |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*


Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.

Analysis Performed By:

Thom Snyder

Approved By:


Frank E. Ehrenfeld, III
Laboratory Director

Date:

SEP 08 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO 63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521718**Client No.:** 125-033**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521719**Client No.:** 125-034**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521720**Client No.:** 125-035**Material Description:** White/Tan**Location:** Insulation/Lag% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

15

Amosite

10

Cellulose

55

10

Chrysotile

10

Mineral Wool

Lab No. 521721**Client No.:** 125-036**Material Description:** White/Tan**Location:** Insulation/Lag% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

3

Chrysotile

15

Mineral Wool

65

3

Amosite

14

Cellulose

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Date:** SEP 03 1996**Approved By:** Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521722**Client No.:** 125-037**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521723**Client No.:** 125-038**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521724**Client No.:** 125-039**Material Description:** White/Black**Location:** Insulation% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

None Detected

None Detected

80

Fibrous Glass

20

Lab No. 521725**Client No.:** 125-040**Material Description:** Gray Insulation**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material


None Detected

None Detected

25

Mineral Wool

75

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Date:****SEP 08 1996****Approved:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521726**Client No.:** 125-041**Material Description:** White/Tan**Location:** Insulation/Lag

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 3 | Chrysotile | 10 | Mineral Wool | 64 |
| 3 | Amosite | 20 | Cellulose | |

Lab No. 521727**Client No.:** 125-042**Material Description:** Sample Not Analyzed**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| Not Analyzed | | Not Analyzed | | |

Lab No. 521728**Client No.:** 125-043**Material Description:** Gray/Tan**Location:** Insulation/Lag

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| 20 | Amosite | 25 | Cellulose | 55 |

Lab No. 521729**Client No.:** 125-044**Material Description:** White Insulation**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 3 | Amosite | 20 | Mineral Wool | 75 |
| 2 | Chrysotile | | | |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Approved By:**Frank E. Ehrenfeld, III
Laboratory Director**Date:**

SEP 02 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, RockyFlats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.:** 521730**Client No.:** 125-045**Material Description:** Tan/Yellow**Location:** Lag/Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|-------------|-------------------------------|
| None Detected | None Detected | 95 | Cellulose | 5 |

Lab No.: 521731**Client No.:** 125-046**Material Description:** White Insulation**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 5 | Amosite | 17 | Mineral Wool | 75 |
| 3 | Chrysotile | | | |

Lab No.: 521732**Client No.:** 125-047**Material Description:** Sample Not Analyzed**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| Not Analyzed | | Not Analyzed | | |

Lab No.: 521733**Client No.:** 125-048**Material Description:** Off White Floor Tile**Location:** w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|---------------|-------------------------------|
| PC 0.50 | Chrysotile | None Detected | None Detected | PC 99.5 |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Date:****SEP 08 1996****Approved By:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis MO 63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521733**Client No.:** 125-048**Material Description:** Off White Floor Tile**Location:** w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|-------------|-------------------------------|
| None Detected | None Detected | 4 | Cellulose | 96 |

Black Tar Mastic

From Above

Lab No. 521734**Client No.:** 125-049**Material Description:** Brown Rubber Comp**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | None Detected | None Detected | 100 |

Lab No. 521735**Client No.:** 125-050**Material Description:** Gray Ceiling Tile**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|--------------|-------------------------------|
| 3 | Amosite | 92 | Mineral Wool | 5 |

Trace Chrysotile

Lab No. 521736**Client No.:** 125-051**Material Description:** Tan/Brown/White**Location:** Sheetrock (No Joint Compound)

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|-------------|-------------------------------|
| None Detected | None Detected | 18 | Cellulose | 80 |

2 Mineral Wool

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Thom Snyder****Analysis Performed By:****Date:** SEP 08 1996**Approved By:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521737**Client No.:** 125-052**Material Description:** White/Tan**Location:** Insulation/Lag% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

5

Chrysotile

23

Mineral Wool

60

2

Amosite

10

Cellulose

Lab No. 521738**Client No.:** 125-053**Material Description:** Sample Not Analyzed**Location:**% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

Not Analyzed

Not Analyzed

Lab No. 521739**Client No.:** 125-054**Material Description:** Tan Floor Tile**Location:** w/Black Mastic% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

PC 0.25

Chrysotile

None Detected

None Detected

PC 99.75

Lab No. 521739**Client No.:** 125-054**Material Description:** Tan Floor Tile**Location:** w/Black Mastic% AsbestosType% Non-Asbestos Fibrous MaterialType% Non-Fibrous Material

None Detected

None Detected

None Detected

None Detected

100

Black Tar Mastic

From Above

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Date:** SEP 08 1996Approved: Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521740**Client No.:** 125-055**Material Description:** Tan Floor Tile**Location:** w/Black Mastic% Asbestos

10

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

90

Lab No. 521740**Client No.:** 125-055**Material Description:** Tan Floor Tile**Location:** w/Black Mastic% Asbestos

5

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

95

Black Tar Mastic

From Above

Lab No. 521741**Client No.:** 125-056**Material Description:** Off White Floor Tile**Location:** (No Mastic)% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

100

Lab No. 521742**Client No.:** 125-057**Material Description:** Tan Floor Tile**Location:** w/Black Mastic% Asbestos

4

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

96

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:****Thom Snyder****Date:****SEP 08 1996****Approved By:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996

Project: DOE, RockyFlats, Bldg 125, 8-22-96

Project No.: 108230

BULK SAMPLE ANALYSIS SUMMARY

Lab No. 521742
Client No.: 125-057

Material Description: Tan Floor Tile
Location: w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|---------------------------------|---------------|--|-------------|-------------------------------|
| None Detected | None Detected | 5 | Cellulose | 95 |
| Black Tar Mastic: From Above | | | | |

Lab No. 521743
Client No.: 125-058

Material Description: Green/White
Location: Floor Tile w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|---------------|-------------------------------|
| 5 | Chrysotile | None Detected | None Detected | 95 |

Lab No. 521743
Client No.: 125-058

Material Description: Green/White
Location: Floor Tile w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|--------------------------------|-------------|--|---------------|-------------------------------|
| 6 | Chrysotile | None Detected | None Detected | 94 |
| Black Tar Mastic From Above | | | | |

Lab No. 521744
Client No.: 125-059

Material Description: Gray/Tan
Location: Insulation/Lag

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| 35 | Amosite | 5 | Cellulose | 60 |

NIST-NVLAP No. 1165

NY-DOH No. 11021

AIHA Lab No. 444

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.

Analysis Performed By: Thom Snyder

Date: SEP 08 1996

Approved By: Frank E. Ehrenfeld, III

Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc
11905 Borman Drive
St. Louis MO 63146**Report Date:** 09/30/1996
Project: DOE, Rocky Flats, Bldg 125, 8-22-96
Project No.: 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521745
Client No.: 125-060**Material Description:** White/Tan
Location: Insulation/Lag

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|-------------|-------------------------------|
| 20 | Amosite | 5 | Cellulose | 60 |
| 15 | Chrysotile | | | |

Lab No. 521746
Client No.: 125-061**Material Description:** White Texture
Location:

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|-------------|-------------------------------|
| None Detected | None Detected | 90 | Cellulose | 10 |

Lab No. 521747
Client No.: 125-062**Material Description:** White Plaster
Location: w/Yellow Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | None Detected | None Detected | 100 |

Lab No. 521747
Client No.: 125-062**Material Description:** White Plaster
Location: w/Yellow Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | None Detected | None Detected | 100 |
| Yellow Mastic | | | | |
| From Above | | | | |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Approved By:** Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 03 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521748**Client No.:** 125-063**Material Description:** Gray Floor Tile**Location:** (No Mastic)% Asbestos

15

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

85

Lab No. 521749**Client No.:** 125-064**Material Description:** Gray Insulation**Location:**% Asbestos

70

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

30

Lab No. 521750**Client No.:** 125-065**Material Description:** White/Tan**Location:** Insulation/Lag% Asbestos

3

Type

Chrysotile

% Non-Asbestos Fibrous Material

20

Type

Mineral Wool

% Non-Fibrous Material

70

2

Amosite

5

Cellulose

Lab No. 521751**Client No.:** 125-066**Material Description:** White**Location:** Insulation/Lag% Asbestos

4

Type

Chrysotile

% Non-Asbestos Fibrous Material

20

Type

Mineral Wool

% Non-Fibrous Material

65

3

Amosite

8

Cellulose

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Approved By:** Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director**Date:** SEP 03 1996

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, RockyFlats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521752**Client No.:** 125-067**Material Description:** White Floor Tile**Location:** w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | None Detected | None Detected | 100 |

Lab No. 521752**Client No.:** 125-067**Material Description:** White Floor Tile**Location:** w/Black Mastic

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|---------------|-------------------------------|
| None Detected | None Detected | None Detected | None Detected | 100 |
| Black Tar Mastic | | | | |
| From Above | | | | |

Lab No. 521753**Client No.:** 125-068**Material Description:** Tan Ceiling Tile**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|---------------|--|--------------|-------------------------------|
| None Detected | None Detected | 50 | Cellulose | 20 |
| | | 30 | Mineral Wool | |

Lab No. 521754**Client No.:** 125-069**Material Description:** Gray Debris**Location:**

| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
|-------------------|-------------|--|---------------|-------------------------------|
| 30 | Chrysotile | None Detected | None Detected | 70 |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** Thom Snyder**Date:** SEP 03 1996**Approved By:** Frank E. Ehrenfeld, IIIFrank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, RockyFlats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521755**Client No.:** 125-070**Material Description:** Black Non Fibrous**Location:**% Asbestos
None DetectedType
None Detected% Non-Asbestos Fibrous Material
None DetectedType
None Detected% Non-Fibrous Material
100**Lab No.** 521756**Client No.:** 125-071**Material Description:** Gray/Blue/White**Location:** Floor Tile w/Black Mastic% Asbestos
PC 1.8Type
Chrysotile% Non-Asbestos Fibrous Material
None detectedType
None Detected% Non-Fibrous Material
PC 98.2**Lab No.** 521756**Client No.:** 125-071**Material Description:** Gray/Blue/White**Location:** Floor Tile w/Black Mastic% Asbestos
None Detected
Black Mastic
From AboveType
None Detected% Non-Asbestos Fibrous Material
TraceType
Cellulose% Non-Fibrous Material
100**Lab No.** 521757**Client No.:** 125-072**Material Description:** Gray Debris**Location:**% Asbestos
30Type
Chrysotile% Non-Asbestos Fibrous Material
None DetectedType
None Detected% Non-Fibrous Material
70**NIST-NVLAP No. 1165****NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:***H. Sonny Robb***Date:** SEP 09 1996

H. Sonny Robb, AIHA-AAR 4883

Approved By:*Frank E. Ehrenfeld, III*Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, RockyFlats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521758**Client No.:** 125-073**Material Description:** White Floor Tile**Location:** w/Tan Mastic% Asbestos

PC 0.25

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

PC 99.75

Lab No. 521758**Client No.:** 125-073**Material Description:** White Floor Tile**Location:** w/Tan Mastic% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

100

Tan Mastic

From Above

Lab No. 521759**Client No.:** 125-074**Material Description:** OffWhite/Tan/Black**Location:** Floor Tile w/Black Mastic% Asbestos

10

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

90

Lab No. 521759**Client No.:** 125-074**Material Description:** OffWhite/Tan/Black**Location:** Floor Tile w/Black Mastic% Asbestos

10

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

90

Black Mastic

From Above

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.*

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:***H. Sonny Robb***Date:**

SEP 09 1998

H. Sonny Robb, AIHA-AAR 4883

Approved By:*Frank E. Ehrenfeld, III*Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521760**Client No.:** 125-075**Material Description:** Black Non Fibrous**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

100

Lab No. 521761**Client No.:** 125-076**Material Description:** Gray/White Fibrous**Location:**% Asbestos

35

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

65

Lab No. 521762**Client No.:** 125-077**Material Description:** Tan/White Fibrous**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

40

Type

Cellulose

% Non-Fibrous Material

50

10

Fibrous Glass

Lab No. 521763**Client No.:** 125-078**Material Description:** Tan/White Fibrous**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

30

Type

Cellulose

% Non-Fibrous Material

55

15

Fibrous Glass

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:**

H. Sonny Robb, AIHA-AAR 4883

Date: SEP 09 1996**Approved By:**Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS**Client:** Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996**Project:** DOE, Rocky Flats, Bldg 125, 8-22-96**Project No.:** 108230**BULK SAMPLE ANALYSIS SUMMARY****Lab No.** 521764**Client No.:** 125-079**Material Description:** Tan/Gray White**Location:** Linoleum w/Tan Mastic% Asbestos

25

Type

Chrysotile

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

75

Lab No. 521764**Client No.:** 125-079**Material Description:** Tan/Gray White**Location:** Linoleum w/Tan Mastic% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

100

Tan mastic

From Above

Lab No. 521765**Client No.:** 125-080**Material Description:** Black Non Fibrous**Location:**% Asbestos

None Detected

Type

None Detected

% Non-Asbestos Fibrous Material

None Detected

Type

None Detected

% Non-Fibrous Material

100

Lab No. 521766**Client No.:** 125-081**Material Description:** Gray/Silver Fibrous**Location:**% Asbestos

70

Type

Chrysotile

% Non-Asbestos Fibrous Material

15

Type

Fibrous Glass

% Non-Fibrous Material

15

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444***This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.***Analysis Method:** EPA 600/R-93/116**Comments:** (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.**Analysis Performed By:** *N. Day-Rohr***Date:**

SEP 09 1996

H. Sonny Robb, AIHA-AAR 4883

Approved By:*Frank E. Ehrenfeld, III*
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Sitex Environmental, Inc

11905 Borman Drive

St. Louis

MO

63146

Report Date: 09/30/1996

Project: DOE, Rocky Flats, Bldg 125, 8-22-96

Project No.: 108230

BULK SAMPLE ANALYSIS SUMMARY

Lab No. 521767

Client No.: 125-082

Material Description: Off White/Tan

Location: Fibrous

% Asbestos

Type

% Non-Asbestos Fibrous Material

Type

% Non-Fibrous Material

PC 5.3

Chrysotile

10

Fibrous Glass

PC 55.2

PC 4.5

Amosite

25

Cellulose

NIST-NVLAP No. 1165

NY-DOH No. 11021

AIHA Lab No. 444

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.

Analysis Performed By:

H. Sonny Robb

H. Sonny Robb, AIHA-AAR 4883

Approved By:

Frank E. Ehrenfeld, III

Frank E. Ehrenfeld, III
Laboratory Director

Date:

SEE 0 8 1996

139

CERTIFICATE OF ANALYSIS

Client: Sitex Environmental, Inc
11905 Borman Drive
St. Louis MO 63146

Report Date: 09/10/1996
Project: Project No. 108230, 8/22/96
Project No.: 108230

BULK SAMPLE ANALYSIS SUMMARY

| | | | | |
|-------------------|---------------|--|-------------------|-------------------------------|
| Lab No. | 521571 | Material Description: | Tan Roof Material | |
| Client No.: | 125-100 | Location: | Insulation | Rocky Flats CO |
| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
| None Detected | None Detected | 85 | Cellulose | 15 |

| | | | | |
|-------------------|---------------|--|---------------------|-------------------------------|
| Lab No. | 521572 | Material Description: | Tan/Black Roof Mat. | |
| Client No.: | 441-100 | Location: | Rubber | Rocky Flats CO |
| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
| None Detected | None Detected | 25 | Cellulose | 74 |
| | | 1 | Synthetic | |
| | | Trace | Fibrous Glass | |

| | | | | |
|-------------------|---------------|--|--------------------|-------------------------------|
| Lab No. | 521573 | Material Description: | White/Black Silver | |
| Client No.: | 441-101 | Location: | Roof Rubber Mat. | Rocky Flats CO |
| <u>% Asbestos</u> | <u>Type</u> | <u>% Non-Asbestos Fibrous Material</u> | <u>Type</u> | <u>% Non-Fibrous Material</u> |
| None Detected | None Detected | Trace | Cellulose | 100 |

NIST-NVLAP No. 1165**NY-DOH No. 11021****AIHA Lab No. 444**

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

Analysis Method: EPA 600/R-93/116

Comments: (PC) Indicates Stratified Point Count Method performed. Method not performed unless stated. PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. Before this material can be considered or treated as non-asbestos containing, confirmation must be made by quantitative TEM.

Analysis Performed By: Al. A. [Signature]Approved By: [Signature]Frank E. Ehrenfeld, III
Laboratory DirectorDate: SEP 03 1996

Beryllium Data Summary

| Sample Number | Sample Location | Result ($\mu\text{g}/100\text{cm}^2$) |
|------------------------|---|--|
| B125 | | |
| 125-10222001-315-101 | Room 109, concrete floor by east wall | <0.1 |
| 125-10222001-315-102 | Room 109, top of electrical track, east wall | <0.1 |
| 125-10222001-315-103 | Room 109, top of red "Fire Reporting Telephone Box", south wall | <0.1 |
| 125-10222001-315-104 | Room 108C, corner of fume hood | <0.1 |
| 125-10222001-315-105 | Plenum, top of HVAC duct, north end | <0.1 |
| 125-10222001-315-106 | Plenum, top of fluorescent light fixture, above north hall | <0.1 |
| 125-10222001-315-107 | Room 125, side of HVAC flue, north end of Mech. Room | <0.1 |
| 125-10222001-315-108 | Room 125, top of air handler in Mech. Room, middle | <0.1 |
| 125-10222001-315-109 | Room 125, top of refrigerated dryer, south end of Mech. Room | <0.1 |
| 125-10222001-315-110 | Plenum, top of electrical conduit above Room 115 | <0.1 |
| 125-10222001-315-111 | Plenum, top of HVAC duct above Room 115 | <0.1 |
| 125-10222001-315-112 | Plenum, top of electrical track above Room 116 | <0.1 |
| 125-10222001-315-113 | Room 108, top of steel cross brace on vertical beam | <0.1 |
| 125-10222001-315-114 | Room 107, in corner on shelf above sink | <0.1 |
| 125-10222001-315-115 | Room 105A, corner of window sill, east wall | <0.1 |
| 125-10222001-315-116 | Room 104, top of steel cross brace on vertical beam | <0.1 |
| 125-10222001-315-117 | Room 104, front edge of entry to fume hood | <0.1 |
| 125-10222001-315-118 | Room 102, top of TP-1 unit in SE corner | <0.1 |
| 125-10222001-315-119 | Room 101D, third book shelf | <0.1 |
| 125-10222001-315-120 | Room 101C, corner of writing desk, SW corner | <0.1 |
| 125-10222001-315-121 | Room 101A, top of floor heater cover | <0.1 |
| 125-10222001-315-122 | Room 120, top of floor heater, west wall | <0.1 |
| 125-10222001-315-123 | Room 122, top of brace above stall in Men's Room | <0.1 |
| 125-10222001-315-124 | Room 123, top of wood & glass case in Ladies' Room | <0.1 |
| 125-10222001-315-125 | Room 124, top of electrical track, south wall of Dark Room | <0.1 |
| B763 | | |
| 763-10222001-315-118 | Survey point 1, window sill, east wall | <0.1 |
| 763-10222001-315-119 | Survey point 2, concrete floor | <0.1 |
| 763-10222001-315-120 | Survey point 3, window sill, east wall | <0.1 |
| 763-10222001-315-121 | Survey point 4, concrete floor | <0.1 |
| 763-10222001-315-122 | Survey point 5, top of electrical panel, north end | <0.1 |
| T900C | | |
| T900C-10232001-315-101 | Top of electrical box, east end | <0.1 |
| T900C-10232001-315-102 | Metal corrugated floor | <0.1 |
| T900C-10232001-315-103 | Angle iron bolted to floor | <0.1 |
| T900C-10232001-315-104 | Metal corrugated floor | <0.1 |
| T900C-10232001-315-105 | Top of electrical receptacle On/Off box, west end | <0.1 |

141

CHEMICAL SAMPLE MAP

Building: T900C

T900C-10232001-315-103

103

T900C-10232001-315-105

105

T900C-10232001-315-104

104






T900C-10232001-315-102

102



T900C-10232001-315-101


101

SURVEY MAP LEGEND

-  Asbestos Sample Location
-  Beryllium Sample Location
-  Lead Sample Location
-  RCRA/CERCLA Sample Location
-  PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp M&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

-  Open/Inaccessible Area
-  Area in Another Survey Unit



1 inch = 12 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GHS Dept. 303-966-770 Prepared for:

DynCorp
THE ART OF TECHNOLOGY



MAP ID: 02-0109/T900c

November 12, 2001

144

PCB Data Summary


| B125 PCB Sample Data | | |
|----------------------------------|-----------------|----------------------------|
| Sample Location | Sample Number | Results (ppb) .. (Aroclor) |
| Rm 125, North Compressor | 02S0007-001.001 | 160 (1254) 100 (1260) |
| Rm 125, Central Compressor | 02S0007-002.001 | 35 (1254) |
| Rm 125, West Wall | 02S0007-003.001 | 250 (1254) |
| Rm 125, South Compressor | 02S0007-004.001 | 310 (1254) |
| Rm 125, South Compressor (dupl.) | 02S0007-005.001 | 390 (1254) 96 (1260) |
| Rm 125, South Air Handler | 02S0007-006.001 | None Detected |
| Rm 109, below hoist | 02S0007-007.001 | 8.1 (1254) |
| Rm 125, South Compressor (swipe) | 02S0007-008.001 | 1600 (1254) |

All results are below the regulatory limit for PCB remediation waste (50 ppm), and below the level for cleanup requirements (25 ppm) as outlined in the *Final Proposed Action Memorandum Remediation of Polychlorinated Biphenyls*, RFETS, May 1995.

045

CHEMICAL SAMPLE MAP

Building: 125




SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ST, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



NOT TO SCALE

U.S. Department of Energy
Rocky Flats Environmental Technology Site
Prepared by: GHS Dept. 303-955-770 Prepared for:
DynCorp
THE ART OF TECHNOLOGY



MAP ID: 02-0109/125-PCB

November 27, 2001

000-A-001

PAGE 1 OF 1

146

ATTACHMENT E

Data Quality Assessment (DQA) Detail

DATA QUALITY ASSESSMENT (DQA) – B125, B763 and T900C

Data used in making management decisions for decommissioning and waste management must be of adequate quality to support decisions. Determination of adequate data quality is accomplished through the DQA. Adequate data quality for decision-making is required by the Kaiser-Hill Quality Assurance Program Manual as well as by the customer (DOE, RFFO; Order 414.1A, Quality Assurance, §4.b.(2)(b)). Regulators and the public also expect decisions and data that are technically and legally defensible.

Verification and validation criteria, used for the DQA, are summarized in tabular format for each category of data, which is based on the type of analytical method. These summaries are provided in Tables E-1 (asbestos), E-2 (beryllium), E-3 (PCBs) and E-4 (radiological surveys). All quality controls were within tolerance with any exceptions noted. A data completeness summary addresses all data acquired for the Project and is given in Table E-5. The DQA checklist for radiological survey data is maintained in the original radiological Survey Package (taken from RSP 16.04).

This report will be submitted to the CERCLA Administrative Record for permanent storage within 30 days of approval by the Regulators. All radiological data are organized into Survey Packages, which correlate to unique (MARSSIM) Survey Units. Chemical data are organized by RIN (Report Identification Number), which contain the entire analytical data package and are traceable to specific sample numbers and corresponding sample locations.

Consistent with EPA's G-4 DQO process, the radiological survey design (for those survey units performed per PDS requirements) was optimized by checking actual measurement results (acquired during pre-demolition surveys) against model output with original estimates. Use of actual sample/survey (result) variances in the MARSSIM DQO model confirms that an adequate number of surveys were acquired; this is indicated by a standard deviation value of less than 0.30 for each individual survey unit. This DQA implements QA guidelines taken from the following MARSSIM sections:

- §4.9, Quality Control
- §8.2, Data Quality Assessment
- §9.0, Quality Assurance & Quality Control
- Appendix E, Assessment Phase of the Data Life Cycle
- Appendix N, Data Validation using Data Descriptors.

SUMMARY

In summary, the data presented in this report have been verified and validated relative to quality requirements and the project decisions as stated in the original DQOs. All data are satisfactory for the decisions made. All media surveyed and sampled yielded results less than their associated action levels, and all with acceptable uncertainties. The Survey Units and structures identified in this RLCR meet the unrestricted-release criteria with the confidences stated herein and the report in total.

Table E-1 V&V of Chemical Results – Asbestos Group 10 (B125, B763 and T900C)

| V&V CRITERIA, CHEMICAL ANALYSES | | DATA PACKAGE | | |
|---------------------------------|--|------------------------------|-------------------------------|---|
| ASBESTOS | METHOD: EPA 600/R-93/116 | LAB ----> | Reservoirs Environmental, Inc | |
| QUALITY REQUIREMENTS | | RIN ----> | 01D0546 | |
| Parameters | | Measure | Frequency | COMMENTS |
| ACCURACY | | below detectable amounts | ≥1 | Semi-quantitative, per (microscopic) visual observation |
| PRECISION | | all below detectable amounts | 15 samples | Semi-quantitative, per (microscopic) visual observation, repeatability established within the sample set |
| REPRESENTATIVENESS | COC | Qualitative | NA | Chain-of-Custody intact: completed paperwork, containers w/ custody seals |
| | Hold times/preservation | Qualitative | NA | Not applicable |
| | Controlling Documents; Maps (Plans, Procedures, etc.) | Qualitative | NA | original Characterization Package (planning document) for field/sampling procedures; thorough documentation of the planning, sampling/analysis process, and data reduction into formats |
| COMPARABILITY | | % by bulk volume | NA | Use of standardized engineering units in the reporting of measurement results |
| COMPLETENESS | Plan vs. Actual samples Usable results vs. unusable | Qualitative | NA | See Table E-5; final number of samples at Certified Inspector's discretion |
| SENSITIVITY | Detection limits | <1% by volume | all measures | |

Table E-2 V&V of Chemical Results-Beryllium Group 10 (B125, B763 and T900C)

| V&V CRITERIA, CHEMICAL ANALYSES | | | DATA PACKAGE | | COMMENTS |
|------------------------------------|--|-------------|--------------------------------------|--|---|
| BERYLLIUM | Preparation: NMAM 7300 METHOD: OSHA ID-125G | | LAB ----> | Johns Manville, Littleton, CO | |
| | | | RIN ----> | 02D0185 | |
| QUALITY REQUIREMENTS Parameters | | | Measure | frequency | |
| ACCURACY | Calibrations | INITIAL | Linear calibration | ≥1 | No qualifications significant enough to change project decisions, i.e. classification of Type 1 Facility confirmed. All results were < 0.1ug/100cm ² . |
| | | continuing | 80%<%R<120% | ≥1 | |
| | LCS/MS | | 80%<%R<120% | ≥1 | |
| | Blanks | lab & field | <MDL | ≥1 | |
| | Interference check std (ICP) | | | NA | |
| PRECISION | LCSD | | 80%<%R<120% (RPD<20%) | ≥1 | |
| | Field duplicate | | all results < RL | ≥1 | |
| REPRESENTATIVENESS | COC | | Qualitative | NA | |
| | Hold times/preservation | | Qualitative | NA | |
| | Maps | | | | |
| | Controlling Documents (Plans, Procedures, etc.) | | Qualitative | NA | |
| COMPARABILITY | Measurement units | | ug/100cm ² | NA | |
| COMPLETENESS | Plan vs. Actual samples | | >95% | NA | |
| | Useable results vs. unusable | | >95% | | |
| SENSITIVITY | Detection Limits | | MDL of 0.012ug/100cm ² | All measures | |

Table E-3 V&V of Chemical Results – PCBs Group 10 Cluster (B125, B763 and T900C)

| V&V CRITERIA, CHEMICAL ANALYSES | | | DATA PACKAGE | | |
|---------------------------------|---|------------|--------------------------------------|------------------------------|---|
| PCBs | METHOD: SW8280 | | LAB ----> | Severn-Trent, Denver, Co. | |
| | | | RIN ----> | 02S0007 | |
| QUALITY REQUIREMENT | | | | | COMMENTS |
| | Parameters | | Measure | frequency | No qualification significant enough to change project decisions, i.e., classification of Type 1 areas confirmed; all PCB concentration were below associated action levels. |
| ACCURACY | Calibrations | INITIAL | $r^2 > 0.99$ | ≥1/batch | |
| | | continuing | 80%<%R<120% | ≥1/batch | |
| | LCS | | 80%<%R<120% | ≥1/batch | |
| | MS | | 75%<%R<125% | ≥1/batch | |
| | Blanks | lab | <MDL | ≥1/batch | |
| PRECISION | MSD | | 75%<%R<125% | ≥1/batch | |
| | field duplicate | | all results < RL | ≥1/batch | |
| REPRESENTATIVENESS | COC | | qualitative | NA | |
| | hold times/preservation | | ≤30 days extract ≤45 day analysis | NA | |
| | Controlling Documents (Plans, Procedures, maps, etc.) | | qualitative | NA | |
| COMPARABILITY | | | ug/kg | NA | |
| COMPLETENESS | Plan vs. Actual samples | | >95% | NA | |
| | usable results vs. unusable | | >95% | | |
| SENSITIVITY | detection limits | | various | all analytes | |

Table E-4 V&V of Radiological Surveys Group 10 Cluster (B125, B763 and T900C)

| V&V CRITERIA, RADIOLGICAL SURVEYS | | | K-H RSP 16.00 Series MARSSIM (NUREG-1575) | | |
|-----------------------------------|--|-------|---|---------------|---|
| QUALITY REQUIREMENTS | | | | | |
| | Parameters | | Measure | frequency | COMMENTS |
| ACCURACY | initial calibrations | | 90%<x<110% | ≥1 | Multi-point calibration through the measurement range encountered in the field |
| | daily source checks | | 80%<x<120% | ≥1/day | |
| | local area background | Field | Typically < 10 dpm | ≥1/day | All local area backgrounds were within expected ranges (i.e., none anomalously high) |
| PRECISION | field duplicate measurements for TSA | | ≥ 5% of real survey points | ≥10% of reals | |
| REPRESENTATIVENESS | MARSSIM gridding methodology (Survey Units G10-001 thru G10-005) | | statistical and biased | NA | Random w/ statistical confidence; biased to improve confidence |
| | Survey Maps | | | NA | Random and biased measurement locations documented to ± 1m |
| | Controlling documents (Characterization Pkg; RSPs) | | qualitative | NA | See Attachment C; original Characterization Package (planning document) for field/sampling procedures; thorough documentation of the planning, sampling/analysis process, and data reduction into formats |
| COMPARABILITY | units of measure | | dpm/100cm ² | NA | Use of standardized engineering units in the reporting of measurement results |
| COMPLETENESS | Plan vs. Actual surveys usable results vs. unusable | | >95% >95% | NA | see Table E-5 for details |
| SENSITIVITY | detection limits | | TSA: ≤50 dpm/100cm ² RA: ≤10 dpm/100cm ² | all measures | MDAs ≤ ½ DCGLw per MARSSIM guidelines |
| | | | | | Measure criteria applies to Survey Units G10-001 thru G10-005 only. |

Table E-5 Data Completeness Summary Group 10 Cluster (B125, B763 and T900C)

| ANALYTE | # Samples Required (incl. Media; Real & QC Samples) | # Taken (Real & QC Samples)^B | Project Decisions (Conclusions & Uncertainty) | Comments (RIN, Analytical Method, Qualifications, etc.) |
|--|--|--|--|--|
| Asbestos Map #000-A-001 | (biased, reals) | (no QC) | ACM (friable and non-friable) present > 1% by volume | 40 CFR 763.86; 5 CCR 1001-10; EPA 600/R-93/116 These samples provided coverage of data gaps not covered by Sitex Environmental Asbestos Inspection Report dated 12/31/96 where the majority of ACM was confirmed. |
| B125 | 15 biased | 8 int./7 ext. | | RIN 02D0184 |
| Beryllium (swipes) Map #000-A-001 | (total, biased, reals) | (real, blanks, QC) 10 QC (total) | No contamination found at any location | OSHA ID-125G |
| B125 | 25 biased (interior) | 25 real | Same | RIN02D0185 |
| B763 | 5 biased (interior) | 5 real | Same | Same RIN |
| T900C | 5 biased (interior) | 5 real | same | Same RIN |
| | | | | [No results above action level (0.2 ug/100cm ²) or investigative level (0.1 ug/100cm ²)] |
| PCBs Map #000-A-001 | Total (reals, duplicates) | | All results were below regulatory limits of 50 ppm | RIN02S0007 |
| B125 | Dependent on walkdown | 7 reals, 1 duplicate | | |
| Radiological Surveys Area G10001- G10005 | | (real, QC) | No contamination found, all values < unrestricted release levels | No results, due to DOE-added radionuclides, above alpha DCGL _w action levels (20 dpm/100cm ² removable, 100 dpm/100cm ² [average per 1m ²]) or above beta DCGL _w action levels (1000 dpm/100cm ² removable, 5000 dpm/100cm ² [average per 1m ²]) |
| • Survey Units | | | | |
| G10-001 | 16 α, β TSA (random) | 32 real, 2 QC | Same | |
| B763 | 2 QC TSA | (interior) | | |
| Breezeway | 16 α, β Smears (random) | | | |

153

Table E-5 Data Completeness Summary Group 10 Cluster (B125, B763 and T900C)

| ANALYTE | # Samples Required (incl. Media; Real & QC Samples) | # Taken (Real & QC Samples) ^B | Project Decisions (Conclusions & Uncertainty) | Comments (RIN, Analytical Method, Qualifications, etc.) |
|--|--|---|---|---|
| G10-002 B763 breezeway exterior | 15 α, β TSA (random) 2 QC TSA 15 α, β Smears (random) | 30 real, 2 QC | Same | 4 sample location investigations - locations were sealed and allowed to decay. Follow-up surveys gave gross and alpha TSA below DCGL _w limits, indicating positive readings are most likely radon daughter products. |
| G10-003 T900C (int./ext.) | 15 α, β TSA (random) 2 QC TSA 15 α, β Smears (random) | 30 real, 2 QC 8 (int.) 7 (ext.) | Same | |
| G10-004 B125 interior | 22 α, β TSA (random)/ 47 α, β TSA (biased) 6 QC TSA 22 α, β Smears (random)/ 47 α, β Smears (biased) | 138 real, 6 QC | Same | An additional 47 biased samples were taken above the minimum required 22 samples to provide adequate coverage of area. |
| G10-005 B125 exterior | 25 α, β TSA (random) 2 QC TSA 25 α, β Smears (random) | 50 real, 2 QC | Same | |


^A # of samples required is estimate only, based on miscellaneous material types; final # of samples at discretion of IH

^B int. – building interior, ext. – building exterior

154/154

CHEMICAL SAMPLE MAP

Building: 125





SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser EB Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



U.S. Department of Energy
Rocky Flats Environmental Technology Site


Prepared by: GIS Dept. 303-660-7707






DynCorp
THE ART OF TECHNOLOGY

MAP ID: 02-0109/B125-Ab November 12, 2001



72

Building: 763 - Breezeway



-  Asbestos Sample Location
-  Beryllium Sample Location
-  Lead Sample Location
-  RCRA/CERCLA Sample Location
-  PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp IAST, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

 Open/Inaccessible Area
 Area in Another Survey Unit

2 

NOT TO SCALE

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

DynCorp
THE ART OF TECHNOLOGY


MAP ID: 02-0109/B763breeze-Chem November 12, 2001

PAGE 1 OF 1

142

CHEMICAL SAMPLE MAP

Building: 125




SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser HD Co., nor DynCorp, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

DynCorp
THE ART OF TECHNOLOGY

MAP ID: 02-0109/B125-Ba November 12, 2001

143